



Stormwater Impact Analysis and Final Design of SCM

The Point / AWH-20000 / August 2021



THE POINT

PACKAGE 2

ROLESVILLE, NORTH CAROLINA

STORMWATER IMPACT ANALYSIS AND FINAL DESIGN OF SCM

CONSTRUCTION DRAWINGS

PLANNING #: SUP 18-09

PROJECT NUMBER:

AWH-20000

DESIGNED BY:

DANIEL WIEBKE, PE, CFM

TOMMY DABOLT

DATE:

AUGUST, 2021



McADAMS

2905 MERIDIAN PARKWAY

DURHAM, NORTH CAROLINA 27713

NC Lic. # C-0293

THE POINT

Stormwater Impact Analysis-CD Package 2

GENERAL DESCRIPTION

The Point is a proposed residential development in Rolesville, North Carolina, located between Highway 401 and East Young Street/Rolesville Road. The development is approximately 300 acres, divided into a northern parcel (to be developed at a later date) and a southern parcel. This Stormwater Impact Analysis covers the development of the southern parcel only. The development will consist of approximately 804 lots, a mixture of townhomes and various types of single-family housing, thirteen stormwater control measures, sidewalks, roadways, greenway trail, and associated infrastructure. At this time stormwater control measures have been developed to a construction level for a portion of the site referred to as CD Package 2. This package includes 5 stormwater control measures; SCM B, G, H, I and J. CD Package 1 ponds are included in the analysis as well to account for a fully developed CD Package 1 prior to CD Package 2 construction.

The project site is located in the Neuse River Basin, and drains to Harris Creek (Peeples Creek / Wake Crossroads Lake) (BIMS # 27-26) and is classified as C;NSW. Per Town of Rolesville regulations, stormwater management on this site shall meet the stormwater management performance standards for development set forth in the Rolesville Unified Development Ordinance Article 7, Section 7.5.4 – Standards.

The regulations are as follows:

(B) Standards Based on Project Density

(4) **Development Standards for High-Density Projects** High-Density Projects shall implement stormwater control measures that comply with each of the following standards, in addition to the General Standards found in subsection B of this Section:

- (a) The measures shall control and treat runoff from the first inch of rain. Runoff volume drawdown time shall be a minimum of 48 hours, but not more than 120 hours.
- (b) All structural stormwater treatment systems used to meet these requirements shall be designed to have a minimum of 85 percent average annual removal for Total Suspended Solids (TSS).
- (c) All Development and Redevelopment projects required to manage storm water shall provide permanent on-site BMPs to lower the nitrogen export amounts as part of the storm water management plan. BMPs are to be in accordance with and as specified in the Design Manual.
- (d) Structural and Non-structural BMPs shall be used to ensure there is no net increase in peak flow leaving the site from the pre-Development conditions for the one-year, 24-hour storm. Runoff volume drawdown time shall be a minimum of 48 hours, but not more than 120 hours.
- (e) General engineering design criteria for all projects shall be in accordance with 15A NCAC 2H .1008(c), as explained in the Design Manual;
- (f) All Development and Redevelopment shall be located outside the Riparian Buffer Zone and the Flood Protection Zone. These Zones shall be in accordance with the following provisions:
 - i. Except where other applicable buffer standards are more restrictive, the Riparian Buffer Zone shall extend a minimum of 50 feet landward of all Perennial and Intermittent Surface Waters. The most restrictive standards shall apply.
 - ii. The Riparian Buffer Zone shall remain undisturbed unless otherwise permitted by this section.
 - iii. The Flood Protection Zone shall extend throughout the FEMA 100-year floodplain as identified on the current Flood Insurance Rate Map (FIRM) published by FEMA. The Flood Protection Zone shall remain undisturbed unless otherwise permitted by this section.

iv. No Development or Redevelopment is permitted within the Riparian Buffer Zone or the Flood Protection Zone except for stream bank or shoreline restoration or stabilization, water dependent structures, and public or private projects such as road crossings and installations, utility crossings and installations, and greenways, where no practical alternatives exist.

v. Permitted activities within the Riparian Buffer Zone and the Flood Protection Zone shall minimize impervious coverage, direct runoff away from surface waters to achieve diffuse flow, and maximize the utilization of Non-structural BMPs.

vi. Where the Riparian Buffer Zone and the Flood Protection Zone both are present adjacent to surface waters, the more restrictive shall apply.

(g) The approval of the stormwater permit shall require an enforceable restriction on property usage that runs with the land, such as recorded deed restrictions or protective covenants, to ensure that future Development and Redevelopment maintains the site consistent with the approved project plans. Buffer widths and locations shall be clearly delineated on all plans, final plat, and as-builts.

(B) General Standards

(1) **Downstream Impact Analysis** The downstream impact analysis must be performed in accordance with the "ten percent rule," and a copy of the analysis must be provided with the permit application. The purpose of the downstream impact analysis is to determine if the project will cause any impacts on flooding or channel degradation downstream of the project site. The analysis must include the assumptions, results and supporting calculations to show safe passage of post-Development design flows downstream. This analysis shall be performed at the outlet(s) of the site, and downstream at each tributary junction to the point(s) in the conveyance system where the area of the portion of the site draining into the system is less than or equal to ten percent of the total drainage area above that point.

(2) Standards for Stormwater Control Measures

(a) **Evaluation According to Contents of Design Manual** All stormwater control measures and stormwater treatment practices (or BMPs) required under this ordinance shall be evaluated by the Stormwater Administrator according to the policies, criteria, and information, including technical specifications and standards and the specific design criteria for each stormwater practice, in the Design Manual. The Stormwater Administrator shall determine whether proposed BMPs will be adequate to meet the requirements of this ordinance.

(b) **Determination of Adequacy; Presumptions and Alternatives** Stormwater treatment practices that are designed, constructed, and maintained in accordance with the criteria and specifications in the Design Manual will be presumed to meet the minimum water quality and quantity performance standards of this ordinance. Whenever an applicant proposes to utilize a practice or practices not designed and constructed in accordance with the criteria and specifications in the Design Manual, the applicant shall have the burden of demonstrating that the practice(s) will satisfy the minimum water quality and quantity performance standards of this ordinance. The Stormwater Administrator may require the applicant to provide the documentation, calculations, and examples necessary for the Stormwater Administrator to determine whether such an affirmative showing is made.

(c) **Separation from Seasonal High Water Table** For BMPs that require a separation from the seasonal high-water table, the separation shall be provided by at least 12 inches of naturally occurring soil above the seasonal high-water table.

CALCULATION METHODOLOGY

- Areas outside of the Package 1 area have been assumed to be undeveloped for the purposes of this analysis.
- Rainfall data for this area in the Rolesville, NC region is from NOAA Atlas 14. This data contains a depth-duration-frequency (DDF) table describing rainfall depth versus time for varying return periods in the area. These rainfall

depths are input into the meteorological model within PondPack for peak flow rate calculations. Please reference the precipitation information within the Miscellaneous Site Information section of this report for additional information.

- On-site and off-site soils were determined using best available GIS data sources.
- Soil Conservation Service Curve Numbers (SCS CN) were selected from Table 2 of the USDA TR-55 for the land use that is most similar to the zoning type or cover condition.
- Land cover conditions for the pre-development condition were taken from survey provided by WithersRavenel and aerial imagery for the site. Land cover conditions for the post-development condition were taken from the proposed layout. Offsite cover conditions were based on GIS-based zoning mapping, provided by the Town of Rolesville.
- The time of concentration was calculated using SCS TR-55 (Segmental Approach, 1986). The Tc flow path can be divided into three segments: overland flow, concentrated flow, and channel flow. The travel time was then computed for each segment, from which the overall time of concentration was determined by taking the sum of each segmental time.
- Existing topographic information used in this analysis is from survey provided by WithersRavenel and QL2 LiDAR from North Carolina's Spatial Data Download.
- PondPack Version V8i was used in determining the pre- & post-development peak flow rates for the 1- and 10-year storm events, as well as routing calculations for the proposed stormwater control measures.
- For 100-year storm routing calculations, a "worst-case" condition was modeled in order to ensure the proposed facility would safely pass the 100-year storm event. The assumptions used in this scenario are as follows:
 - The starting water surface elevation in the facility, just prior to the 100-year storm event, is at the invert of the secondary orifice. This scenario could occur as a result of a clogged primary orifice or a rainfall event that lingers for several days. This could also occur as a result of several rainfall events in a series, before the low-flow orifice has an opportunity to draw down the storage pool.
 - Approximately 1-foot of freeboard is provided between the peak elevation during the "worst-case" scenario and the top of the dam for the proposed facility.

To meet the above Town of Rolesville standards, thirteen stormwater control measures (SCMs) have been proposed.

DISCUSSION OF RESULTS

PEAK RUNOFF CONTROL REQUIREMENTS

As shown in the Summary of Results section of this SIA, the proposed stormwater control measures provide the necessary peak runoff control for the proposed build-out condition of the development such that there are no calculated increases in the 1- and 10-year storm events at any point of analysis leaving the site.

POLLUTANT AND NUTRIENT CONTROL REQUIREMENTS

The proposed SCM is designed to the Minimum Design Criteria of the NCDEQ Stormwater Design Manual. Therefore, the proposed development is treated for 85% TSS removal and provides nitrogen and phosphorus treatment.

CONCLUSION

If the development on this tract is built as proposed within this report, then the requirements set forth in Town of Rolesville regulations will be met without additional stormwater management facilities. However, modifications to the proposed development may require that this analysis be revised. Some modifications that would **require** this analysis to be revised include:

1. The proposed site impervious surface exceeds the amount accounted for in this report.
2. The post-development watershed breaks change significantly from those used to prepare this report.

The above modifications may result in the assumptions within this report becoming invalid. The computations within this report will need to be revisited if any of the above conditions become apparent as development of the proposed site moves forward.

1	SUMMARY OF RESULTS
2	MISCELANEOUS SITE INFORMATION
3	PRE-DEVELOPMENT HYDROLOGIC CALCULATIONS
4	POST-DEVELOPMENT HYDROLOGIC CALCULATIONS
5	STORMWATER CONTROL MEASURE 'B' DESIGN FILES
6	STORMWATER CONTROL MEASURE 'G' DESIGN FILES
7	STORMWATER CONTROL MEASURE 'H' DESIGN FILES
8	STORMWATER CONTROL MEASURE 'I' DESIGN FILES
9	STORMWATER CONTROL MEASURE 'J' DESIGN FILES

SUMMARY OF RESULTS

SUMMARY OF RESULTS

RELEASE RATE MANAGEMENT RESULTS

POINT OF ANALYSIS #1			
Return Period	Pre-Dev [cfs]	Post-Dev [cfs]	% Increase [%]
1-Year	283.5	227.0	-20%
10-Year	545.3	521.3	-4%
POINT OF ANALYSIS #2			
Return Period	Pre-Dev [cfs]	Post-Dev [cfs]	% Increase [%]
1-Year	77.3	70.4	-9%
10-Year	153.0	139.4	-9%
POINT OF ANALYSIS #3			
Return Period	Pre-Dev [cfs]	Post-Dev [cfs]	% Increase [%]
1-Year	8.2	6.0	-26%
10-Year	21.2	15.1	-29%
POINT OF ANALYSIS #4			
Return Period	Pre-Dev [cfs]	Post-Dev [cfs]	% Increase [%]
1-Year	344.2	289.2	-16%
10-Year	704.1	675.0	-4%
POINT OF ANALYSIS #5			
Return Period	Pre-Dev [cfs]	Post-Dev [cfs]	% Increase [%]
1-Year	359.7	353.5	-2%
10-Year	787.2	787.1	0%

SUMMARY OF RESULTS

STORMWATER CONTROL MEASURE 'B' SUMMARY

Design Drainage Area =	10.26	ac
Design Impervious Area =	6.11	ac
% Impervious =	59.6%	
Top of Dam =	382.00	ft
NWSE =	376.00	ft
WQv Ponding Elevation =	377.86	ft
Required Main Pool Surface Area at NWSE =	6,766	sf
Total Surface Area Provided at NWSE =	9,314	sf
Provided Main Pool Surface Area at NWSE =	6,928	sf
WQv Orifice Diameter =	2.00	in
WQv Orifice Invert Elevation =	376.00	ft
Riser Size =	4' x 4'	
Riser Crest =	380.00	ft
Number of Orifices =	3	
Orifice Invert Elevation =	379.00	ft
Orifice Width =	36.00	in
Orifice Height =	6.00	in
Barrel Diameter =	24	in
# of Barrels =	1	
Upstream Invert =	375.00	ft
Downstream Invert =	374.00	ft
Length =	50	ft
Slope =	0.0200	ft/ft

STORMWATER CONTROL MEASURE 'B' ROUTING RESULTS

Return Period	Inflow [cfs]	Outflow [cfs]	Max. WSE [ft]
1-Year	29.9	1.6	379.07
10-Year	55.8	22.5	380.12
25-Year	64.7	31.5	380.57
100-Year	77.5	34.7	381.19

SUMMARY OF RESULTS

Freeboard [ft]
2.93
1.88
1.43
0.81

SUMMARY OF RESULTS

STORMWATER CONTROL MEASURE 'G' SUMMARY

Design Drainage Area =	13.66	ac
Design Impervious Area =	8.16	ac
% Impervious =	59.8%	
Top of Dam =	346.00	ft
NWSE =	340.00	ft
WQv Ponding Elevation =	341.58	ft
Required Main Pool Surface Area at NWSE =	11,552	sf
Total Surface Area Provided at NWSE =	15,673	sf
Provided Main Pool Surface Area at NWSE =	12,421	sf
WQv Orifice Diameter =	2.50	in
WQv Orifice Invert Elevation =	340.00	ft
Riser Size =	5' x 5'	
Riser Crest =	345.00	ft
Number of Weirs =	3	
Weir Length =	48.00	in
Orifice Invert El. =	343.75	ft
Barrel Diameter =	36	in
# of Barrels =	1	
Upstream Invert =	339.50	ft
Downstream Invert =	339.00	ft
Length =	48.5	ft
Slope =	0.0103	ft/ft

STORMWATER CONTROL MEASURE 'G' ROUTING RESULTS

Return Period	Inflow [cfs]	Outflow [cfs]	Max. WSE [ft]
1-Year	45.5	0.4	343.67
10-Year	79.4	20.3	344.42
25-Year	90.8	40.9	344.83
100-Year	107.2	62.7	345.33

SUMMARY OF RESULTS

Freeboard [ft]
2.33
1.58
1.17
0.67

SUMMARY OF RESULTS

STORMWATER CONTROL MEASURE 'H' SUMMARY

Design Drainage Area =	16.40	ac
Design Impervious Area =	9.15	ac
% Impervious =	55.8%	
Top of Dam =	336.00	ft
NWSE =	330.00	ft
WQv Ponding Elevation =	331.54	ft
Required Main Pool Surface Area at NWSE =	13,269	sf
Total Surface Area Provided at NWSE =	18,403	sf
Provided Main Pool Surface Area at NWSE =	14,123	sf
WQv Orifice Diameter =	2.75	in
WQv Orifice Invert Elevation =	330.00	ft
Riser Size =	6' x 6'	
Riser Crest =	335.00	ft
Number of Orifices =	3	
Orifice Invert Elevation =	333.75	ft
Orifice Width =	60.00	in
Orifice Height =	6.00	in
Barrel Diameter =	42	in
# of Barrels =	1	
Upstream Invert =	329.50	ft
Downstream Invert =	327.00	ft
Length =	200	ft
Slope =	0.0125	ft/ft

STORMWATER CONTROL MEASURE 'H' ROUTING RESULTS

Return Period	Inflow [cfs]	Outflow [cfs]	Max. WSE [ft]
1-Year	52.3	0.4	333.74
10-Year	93.4	23.5	334.41
25-Year	107.2	36.1	334.98
100-Year	127.2	71.8	335.54

SUMMARY OF RESULTS

Freeboard [ft]
2.26
1.59
1.02
0.46

SUMMARY OF RESULTS

STORMWATER CONTROL MEASURE 'I' SUMMARY

Design Drainage Area =	8.37	ac
Design Impervious Area =	4.54	ac
% Impervious =	54.3%	
Top of Dam =	324.00	ft
NWSE =	318.00	ft
WQv Ponding Elevation =	319.67	ft
Required Main Pool Surface Area at NWSE =	5,024	sf
Total Surface Area Provided at NWSE =	7,619	sf
Provided Main Pool Surface Area at NWSE =	5,157	sf
WQv Orifice Diameter =	1.75	in
WQv Orifice Invert Elevation =	318.00	ft
Riser Size =	5' x 5'	
Riser Crest =	323.00	ft
Number of Orifices =	3	
Orifice Invert Elevation =	322.00	ft
Orifice Width =	48.00	in
Orifice Height =	9.00	in
Barrel Diameter =	36	in
# of Barrels =	1	
Upstream Invert =	317.00	ft
Downstream Invert =	316.00	ft
Length =	48.5	ft
Slope =	0.0206	ft/ft

STORMWATER CONTROL MEASURE 'I' ROUTING RESULTS

Return Period	Inflow [cfs]	Outflow [cfs]	Max. WSE [ft]
1-Year	24.4	0.2	321.73
10-Year	45.5	15.2	322.43
25-Year	52.8	28.6	322.81
100-Year	63.2	45.9	323.22

SUMMARY OF RESULTS

Freeboard [ft]
2.27
1.57
1.19
0.78

SUMMARY OF RESULTS

STORMWATER CONTROL MEASURE 'J' SUMMARY

Design Drainage Area =	14.19	ac
Design Impervious Area =	6.69	ac
% Impervious =	47.2%	
Top of Dam =	316.00	ft
NWSE =	310.00	ft
WQv Ponding Elevation =	311.65	ft
Required Main Pool Surface Area at NWSE =	8,495	sf
Total Surface Area Provided at NWSE =	11,895	sf
Provided Main Pool Surface Area at NWSE =	8,977	sf
WQv Orifice Diameter =	2.25	in
WQv Orifice Invert Elevation =	310.00	ft
Riser Size =	5' x 5'	
Riser Crest =	314.00	ft
Number of Orifices =	1	
Orifice width =	48.00	in
Orifice height =	6.00	in
Orifice Invert El. =	313.00	ft
Barrel Diameter =	36	in
# of Barrels =	1	
Upstream Invert =	309.50	ft
Downstream Invert =	309.00	ft
Length =	48.5	ft
Slope =	0.0103	ft/ft

STORMWATER CONTROL MEASURE 'J' ROUTING RESULTS

Return Period	Inflow [cfs]	Outflow [cfs]	Max. WSE [ft]
1-Year	37.4	1.2	313.11
10-Year	73.4	23.0	314.35
25-Year	85.9	48.2	314.72
100-Year	104.1	74.0	315.10

SUMMARY OF RESULTS

Freeboard [ft]
2.89
1.65
1.28
0.90

Total Nitrogen Analysis Area =	303.05	acres
Max. TN-Export w/o Offset Payment =	1090.99	lbs/yr
	3.60	lbs/ac/yr
Computed TN-Export Before Treatment =	956.68	lbs/yr
	3.16	lbs/ac/yr
Computed TN-Export After Treatment =	754.71	lbs/yr
	2.49	lbs/ac/yr

**POST-DEVELOPMENT
NITROGEN EXPORT CALCULATIONS**

To SWMF

METHOD 2:

Quantifying TN Export from Residential / Industrial / Commercial Developments when Footprints of all Impervious Surfaces are shown.

- STEP 1:** Determine the area for each type of land use and enter in Column (2).
STEP 2: Total the areas for each type of land use and enter at the bottom of Column (2).
STEP 3: Multiply the areas in Column (2) by the TN export coefficients in Column (3) and enter in Column (4).
STEP 4: Total the TN exports for each type of land use and enter at the bottom of Column (4).
STEP 5: Determine the export coefficient for the site by dividing the total TN export from uses at the bottom of Column (4) by the total area at the bottom of Column (2).

(1) Type of Land Cover	(2) Area [acres]	(3) TN export coeff. (lbs/ac/yr)	(4) TN export from use (lbs/yr)
<i>Permanently protected undisturbed open space</i> (forest, unmown meadow)	0.00	0.6	0.00
<i>Permanently protected managed open space</i> (grass, landscaping, etc.)	75.85	1.2	91.02
<i>Impervious surfaces</i> (roads, parking lots, driveways, roofs, paved storage areas, etc.)	27.46	21.2	582.21
TOTAL	103.31	---	673.23

<== Includes BMP Area

Total TN Export = 6.5 lbs/ac/yr
 % impervious = 26.6%

**POST-DEVELOPMENT
NITROGEN EXPORT CALCULATIONS**

Bypass Area

METHOD 2:


Quantifying TN Export from Residential / Industrial / Commercial Developments when Footprints of all Impervious Surfaces are shown.

- STEP 1:** Determine the area for each type of land use and enter in Column (2).
STEP 2: Total the areas for each type of land use and enter at the bottom of Column (2).
STEP 3: Multiply the areas in Column (2) by the TN export coefficients in Column (3) and enter in Column (4).
STEP 4: Total the TN exports for each type of land use and enter at the bottom of Column (4).
STEP 5: Determine the export coefficient for the site by dividing the total TN export from uses at the bottom of Column (4) by the total area at the bottom of Column (2).

(1) Type of Land Cover	(2) Area [acres]	(3) TN export coeff. (lbs/ac/yr)	(4) TN export from use (lbs/yr)
<i>Permanently protected undisturbed open space</i> (forest, unmown meadow)	0.00	0.6	0.00
<i>Permanently protected managed open space</i> (grass, landscaping, etc.)	190.17	1.2	228.21
<i>Impervious surfaces</i> (roads, parking lots, driveways, roofs, paved storage areas, etc.)	2.61	21.2	55.24
TOTAL	192.78	---	283.45

Total TN Export = 1.5 lbs/ac/yr
 % impervious = 1.4%

MISCELLANEOUS SITE INFORMATION



NC Center for Geographic Information & Analysis, Esri, HERE, Garmin, ©
OpenStreetMap contributors



0 750 1,500 3,000 Feet
1 inch = 1,500 feet

THE POINT


SITE AERIAL MAP

PROJECT #: AWH-20000

ROLESVILLE, NORTH CAROLINA



MCADAMS



0 1,000 2,000 4,000 Feet
1 inch = 2,000 feet

THE POINT
USGS TOPO MAP
PROJECT #: AWH-20000
ROLESVILLE, NORTH CAROLINA



MCADAMS

. 0315

NEUSE RIVER BASIN

Name of Stream	Description	Class	Class Date	Index No.
NEUSE RIVER	From a point 0.5 mile upstream of Town of Wake Forest proposed water supply intake to Town of Wake Forest proposed water supply intake	WS-IV;NSW,CA	07/01/04	27-(22)
NEUSE RIVER	From Town of Wake Forest proposed water supply intake to mouth of Beddingfield Creek	C;NSW	08/03/92	27-(22.5)
Smith Creek	From source to a point 0.3 mile downstream of Franklin-Wake County Line	WS-II;Hqw,NSW	08/03/92	27-23-(1)
Smith Creek (Wake Forest Reservoir)	From a point 0.3 mile downstream of Franklin-Wake County Line to dam at Wake Reservoir	WS-II;Hqw,NSW, CA	08/03/92	27-23-(1.5)
Smith Creek	From dam at Wake Forest Reservoir to Neuse River	C;NSW	05/01/88	27-23-(2)
Austin Creek (Mitchell Pond)	From source to Smith Creek	C;NSW	07/01/96	27-23-3
Hatters Branch	From source to Smith Creek	C;NSW	05/01/88	27-23-4
Spring Branch	From source to Hatters Branch	C;NSW	05/01/88	27-23-4-1
Sanford Creek	From source to Smith Creek	C;NSW	05/01/88	27-23-5
Toms Creek (Mill Creek)	From source to Neuse River	C;NSW	05/01/88	27-24
Perry Creek (Greshams Lake)	From source to dam at Greshams Lake	B;NSW	05/01/88	27-25-(1)
Perry Creek	From dam at Greshams Lake to Neuse River	C;NSW	05/01/88	27-25-(2)
Unnamed Tributary near Neuse	From source to dam at Camp Durant	B;NSW	05/01/88	27-25-3-(1)
Unnamed Tributary near Neuse	From dam at Camp Durant to Perry Creek	C;NSW	05/01/88	27-25-3-(2)
Harris Creek (Peeples Creek) (Wake Crossroads Lake)	From source to Neuse River	C;NSW	05/01/88	27-26
Hodges Mill Creek (Lake Mirl)	From source to water intake at Lake Mirl	B;NSW	05/01/88	27-26-1-(1)
Hodges Mill Creek	From water intake at Lake Mirl to Harris Creek	C;NSW	05/01/88	27-26-1-(2)
Beaverdam Creek (west side of Neuse River)	From source to Neuse River	C;NSW	05/01/88	27-27
Rocky Creek	From source to Neuse River	C;NSW	05/01/88	27-28
Beaverdam Creek (east side of Neuse River) (Neuseco Lake, Beaverdam Lake)	From source to Neuse River	C;NSW	05/01/88	27-29
Bridges Creek (Bridges Lake)	From source to Neuse River	C;NSW	05/01/88	27-30
Milburnie Creek (Milburnie Lake)	From source to Neuse River	C;NSW	05/01/88	27-31
Mango Creek	From source to Neuse River	C;NSW	05/01/88	27-32
Crabtree Creek	From source to backwaters of Crabtree Lake	C;NSW	05/01/88	27-33-(1)
Turkey Creek	From source to Crabtree Creek	C;NSW	05/01/88	27-33-2
Coles Branch	From source to Crabtree Creek	C;NSW	05/01/88	27-33-3
South Fork Coles Branch	From source to Coles Branch	C;NSW	05/01/88	27-33-3-1
Crabtree Creek (Crabtree Lake)	From backwaters of Crabtree Lake to mouth of Richlands Creek	B;NSW	04/01/94	27-33-(3.5)



This digital Flood Insurance Rate Map (FIRM) was produced through a unique cooperative partnership between the State of North Carolina and the Federal Emergency Management Agency (FEMA). The State of North Carolina has implemented a long term approach to floodplain management to decrease the costs associated with flooding. This is demonstrated by the State's commitment to map flood hazard areas at the local level. As a part of this effort, the State of North Carolina has joined in a Cooperating Technical State agreement with FEMA to produce and maintain this digital FIRM.

FLOOD HAZARD INFORMATION

SEE FIS REPORT FOR ZONE DESCRIPTIONS AND INDEX MAP
THE INFORMATION DEPICTED ON THIS MAP AND SUPPORTING
DOCUMENTATION ARE ALSO AVAILABLE IN DIGITAL FORMAT AT
[HTTP://FRIS.NC.GOV/FRIS](http://FRIS.NC.GOV/FRIS)

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE)
		With BFE or Depth Zone AE, AO, AH, VE, AR
		Regulatory Floodway
OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% Annual Chance Flood with Average Depth Less Than One Foot or With Drainage Areas of Less Than One Square Mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
OTHER AREAS		Area with Reduced Flood Risk due to Levee See Notes Zone X
		Areas Determined to be Outside the 0.2% Annual Chance Floodplain Zone X
GENERAL STRUCTURES		Channel, Culvert, or Storm Sewer Accredited or Provisionally Accredited Levee, Dike, or Floodwall
		Non-accredited Levee, Dike, or Floodwall
OTHER FEATURES		North Carolina Geodetic Survey bench mark
		National Geodetic Survey bench mark
		Contractor Est. NCFMP Survey bench mark
		Cross Sections with 1% Annual Chance Water Surface Elevation (BFE)
		Coastal Transect
		Coastal Transect Baseline
		Profile Baseline
		Hydrographic Feature
		Limit of Study
		Jurisdiction Boundary

NOTES TO USERS

For information and questions about this map, available products associated with this FIRM including historic versions of this FIRM, how to order products or the National Flood Insurance Program in general, please call the FEMA Map Information eXchange at 1-877-FEMA-MAP (1-877-336-2627) or visit the FEMA Map Service Center website at <http://msc.fema.gov>. An accompanying Flood Insurance Study report, Letter of Map Revision (LOMR) or Letter of Map Amendment (LOMA) revising portions of this panel, and digital versions of this FIRM may be available. Visit the North Carolina Floodplain Mapping Program website at <http://www.ncfloodmaps.com>, or contact the FEMA Map Service Center.

Communities annexing land on adjacent FIRM panels must obtain a current copy of the adjacent panel as well as the current FIRM Index. These may be ordered directly from the Map Service Center at the number listed above. For community and countywide map dates refer to the Flood Insurance Study report for this jurisdiction. To determine if flood insurance is available in the community, contact your insurance agent or call the National Flood Insurance Program at 1-800-638-6620.

Base map information shown on this FIRM was provided in digital format by the North Carolina Floodplain Mapping Program (NCFMP). The source of this information can be determined from the metadata available in the digital FLOOD database and in the Technical Support Data Notebook (TSDN).

ACCREDITED LEEVE NOTES TO USERS: If an accredited levee note appears on this panel check with your local community to obtain more information, such as the estimated level of protection provided (which may exceed the 1-percent-annual-chance level) and Emergency Action Plan, on the levee system(s) shown as providing protection. To mitigate flood risk in residual risk areas, property owners and residents are encouraged to consider flood insurance and floodproofing or other protective measures. For more information on flood insurance, interested parties should visit the FEMA Website at <http://www.fema.gov/business/index.shm>.

PROVISIONALLY ACCREDITED LEEVE NOTES TO USERS: If a Provisionally Accredited Levee (PAL) note appears on this panel, check with your local community to obtain more information, such as the estimated level of protection provided (which may exceed the 1-percent-annual-chance level) and Emergency Action Plan, on the levee system(s) shown as providing protection. To maintain accreditation, the levee owner or community is required to submit the data and documentation necessary to comply with Section 65.10 of the NFIP regulations. If the community or owner does not provide the necessary data and documentation or if the data and documentation provided indicates the levee system does not comply with Section 65.10 requirements, FEMA will revise the flood hazard and risk information for this area to reflect de-accreditation of the levee system. To mitigate flood risk in residual risk areas, property owners and residents are encouraged to consider flood insurance and floodproofing or other protective measures. For more information on flood insurance, interested parties should visit the FEMA Website at <http://www.fema.gov/business/index.shm>.

LIMIT OF MODERATE WAVE ACTION NOTES TO USERS: For some coastal flooding zones the AE Zone category has been divided by a Limit of Moderate Wave Action (LMWA). The LMWA represents the approximate landward limit of the 1.5-foot breaking wave. The effects of wave hazards between the VE Zone and the LMWA (or between the shoreline and the LMWA for areas where VE Zones are not identified) will be similar to, but less severe than those in the VE Zone.


COASTAL BARRIER RESOURCES SYSTEM (CBRS) NOTE

This map may include approximate boundaries of the CBRS for informational purposes only. Flood insurance is not available within CBRS areas for structures that are newly built or substantially improved on or after the date(s) indicated on the map. For more information see http://www.fws.gov/habitatconservation/coastal_barrier.html, the FIS Report, or call the U.S. Fish and Wildlife Service Customer Service Center at 1-800-344-WILD.


CBRS Area Otherwise Protected Area

LOGO LOGO

SCALE



PANEL LOCATOR



FEMA National Flood Insurance Program


NORTH CAROLINA FLOODPLAIN MAPPING PROGRAM NATIONAL FLOOD INSURANCE PROGRAM FLOOD INSURANCE RATE MAP

NORTH CAROLINA


PANEL 1768

Panel Contains:

COMMUNITY	CID	PANEL	SUFFIX
ROLESVILLE, TOWN OF WAKE COUNTY	370468	1768	J
	370368	1768	J



MAP NUMBER
3720176800J
MAP REVISED
05/02/06



N

0 750 1,500 3,000 Feet

1 inch = 1,500 feet

THE POINT



SOIL MAP

PROJECT #: AWH-20000

ROLESVILLE, NORTH CAROLINA

MCADAMS

Hydrologic Soil Group—Wake County, North Carolina (Property Line)




**Natural Resources
Conservation Service**

Web Soil Survey
National Cooperative Soil Survey

6/3/2020
Page 1 of 4

MAP LEGEND

Area of Interest (AOI)









 Area of Interest (AOI)

Soils

Soil Rating Polygons





 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Lines


 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Points






 A
 A/D
 B
 B/D

 C
 C/D
 D
 Not rated or not available


Water Features

 Streams and Canals

Transportation

 Rails
 Interstate Highways
 US Routes
 Major Roads
 Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Wake County, North Carolina
Survey Area Data: Version 18, Sep 16, 2019

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Oct 11, 2019—Oct 19, 2019

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
AaA	Altavista fine sandy loam, 0 to 4 percent slopes, rarely flooded	C	4.1	1.4%
AuA	Augusta fine sandy loam, 0 to 2 percent slopes, rarely flooded	C/D	10.1	3.3%
ChA	Chewacla and Wehadkee soils, 0 to 2 percent slopes, frequently flooded	B/D	27.0	8.9%
HeB	Helena sandy loam, 2 to 6 percent slopes	D	7.1	2.4%
RgB	Rawlings-Rion complex, 2 to 6 percent slopes	C	43.5	14.4%
RgC	Rawlings-Rion complex, 6 to 10 percent slopes	C	45.6	15.1%
RgD	Rawlings-Rion complex, 10 to 15 percent slopes	C	15.0	5.0%
W	Water		9.7	3.2%
WaB	Wake-Rolesville complex, 2 to 6 percent slopes, very rocky	D	7.4	2.4%
WaC	Wake-Rolesville complex, 6 to 10 percent slopes, very rocky	D	29.0	9.6%
WaD	Wake-Rolesville complex, 10 to 15 percent slopes, very rocky	D	51.1	16.9%
WaE	Wake-Rolesville complex, 15 to 25 percent slopes, very rocky	D	28.9	9.6%
WeB	Wedowee sandy loam, 2 to 6 percent slopes	D	0.2	0.1%
WfB	Wedowee-Saw complex, 2 to 6 percent slopes	D	22.9	7.6%
WgC	Wedowee-Urban land complex, 6 to 15 percent slopes	D	0.1	0.0%
Totals for Area of Interest			301.6	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher



NOAA Atlas 14, Volume 2, Version 3
Location name: Wake Forest, North Carolina, USA*
Latitude: 35.9053°, Longitude: -78.452°
Elevation: 354.67 ft**

* source: ESRI Maps

** source: USGS



POINT PRECIPITATION FREQUENCY ESTIMATES

G.M. Bonnin, D. Martin, B. Lin, T. Parzybok, M. Yekta, and D. Riley

NOAA, National Weather Service, Silver Spring, Maryland

[PF tabular](#) | [PF graphical](#) | [Maps & aerals](#)

PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches) ¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.403 (0.369-0.442)	0.468 (0.429-0.512)	0.534 (0.489-0.582)	0.600 (0.548-0.654)	0.666 (0.606-0.726)	0.718 (0.651-0.783)	0.765 (0.690-0.834)	0.807 (0.723-0.881)	0.853 (0.758-0.932)	0.895 (0.789-0.979)
10-min	0.644 (0.590-0.705)	0.749 (0.687-0.818)	0.855 (0.783-0.933)	0.959 (0.877-1.05)	1.06 (0.966-1.16)	1.14 (1.04-1.25)	1.22 (1.10-1.33)	1.28 (1.15-1.40)	1.35 (1.20-1.47)	1.41 (1.24-1.54)
15-min	0.806 (0.738-0.882)	0.942 (0.863-1.03)	1.08 (0.991-1.18)	1.21 (1.11-1.32)	1.35 (1.22-1.47)	1.45 (1.31-1.58)	1.54 (1.39-1.68)	1.61 (1.45-1.76)	1.70 (1.51-1.86)	1.77 (1.56-1.94)
30-min	1.10 (1.01-1.21)	1.30 (1.19-1.42)	1.54 (1.41-1.68)	1.76 (1.61-1.92)	1.99 (1.81-2.17)	2.18 (1.98-2.38)	2.35 (2.12-2.57)	2.51 (2.25-2.74)	2.70 (2.40-2.95)	2.87 (2.52-3.14)
60-min	1.38 (1.26-1.51)	1.63 (1.50-1.78)	1.97 (1.81-2.15)	2.29 (2.09-2.50)	2.65 (2.42-2.89)	2.96 (2.68-3.22)	3.24 (2.92-3.53)	3.52 (3.16-3.85)	3.88 (3.45-4.24)	4.18 (3.69-4.58)
2-hr	1.61 (1.46-1.78)	1.92 (1.75-2.10)	2.34 (2.13-2.56)	2.75 (2.49-3.01)	3.23 (2.91-3.54)	3.66 (3.28-4.00)	4.07 (3.63-4.45)	4.49 (3.98-4.91)	5.04 (4.42-5.51)	5.52 (4.80-6.05)
3-hr	1.71 (1.55-1.89)	2.03 (1.85-2.24)	2.49 (2.26-2.74)	2.94 (2.67-3.24)	3.50 (3.15-3.84)	3.99 (3.58-4.39)	4.49 (3.98-4.92)	5.00 (4.41-5.48)	5.69 (4.96-6.24)	6.32 (5.45-6.95)
6-hr	2.05 (1.87-2.26)	2.44 (2.23-2.68)	2.99 (2.72-3.28)	3.54 (3.22-3.88)	4.22 (3.82-4.62)	4.84 (4.35-5.29)	5.46 (4.86-5.96)	6.12 (5.39-6.67)	7.00 (6.10-7.64)	7.82 (6.72-8.55)
12-hr	2.41 (2.21-2.66)	2.87 (2.64-3.15)	3.54 (3.24-3.88)	4.21 (3.84-4.62)	5.07 (4.59-5.53)	5.85 (5.26-6.36)	6.64 (5.91-7.22)	7.49 (6.59-8.14)	8.66 (7.50-9.41)	9.76 (8.32-10.6)
24-hr	2.86 (2.66-3.08)	3.46 (3.22-3.73)	4.35 (4.04-4.69)	5.06 (4.69-5.44)	6.02 (5.57-6.49)	6.80 (6.27-7.32)	7.60 (6.98-8.19)	8.43 (7.71-9.09)	9.58 (8.71-10.3)	10.5 (9.50-11.3)
2-day	3.32 (3.09-3.57)	3.99 (3.72-4.30)	4.98 (4.64-5.37)	5.77 (5.35-6.21)	6.83 (6.32-7.36)	7.68 (7.09-8.27)	8.56 (7.87-9.22)	9.46 (8.66-10.2)	10.7 (9.74-11.6)	11.7 (10.6-12.7)
3-day	3.52 (3.28-3.77)	4.23 (3.94-4.54)	5.25 (4.89-5.63)	6.06 (5.64-6.50)	7.17 (6.64-7.69)	8.05 (7.44-8.64)	8.96 (8.25-9.62)	9.89 (9.07-10.6)	11.2 (10.2-12.1)	12.2 (11.1-13.2)
4-day	3.72 (3.47-3.98)	4.46 (4.17-4.77)	5.52 (5.15-5.90)	6.35 (5.92-6.79)	7.50 (6.96-8.01)	8.42 (7.79-9.00)	9.36 (8.63-10.0)	10.3 (9.49-11.1)	11.7 (10.7-12.5)	12.7 (11.6-13.7)
7-day	4.31 (4.04-4.61)	5.15 (4.82-5.50)	6.29 (5.88-6.71)	7.19 (6.72-7.68)	8.43 (7.85-9.00)	9.42 (8.75-10.1)	10.4 (9.66-11.2)	11.5 (10.6-12.3)	12.9 (11.8-13.9)	14.1 (12.8-15.1)
10-day	4.91 (4.61-5.24)	5.85 (5.48-6.23)	7.04 (6.60-7.50)	7.99 (7.47-8.50)	9.26 (8.64-9.86)	10.3 (9.55-10.9)	11.3 (10.5-12.0)	12.3 (11.4-13.2)	13.7 (12.6-14.7)	14.8 (13.6-15.9)
20-day	6.59 (6.20-7.02)	7.79 (7.32-8.29)	9.23 (8.67-9.81)	10.4 (9.72-11.0)	11.9 (11.1-12.7)	13.1 (12.2-14.0)	14.3 (13.3-15.3)	15.6 (14.5-16.6)	17.3 (16.0-18.5)	18.6 (17.1-19.9)
30-day	8.18 (7.72-8.69)	9.63 (9.08-10.2)	11.2 (10.6-11.9)	12.5 (11.7-13.2)	14.1 (13.2-15.0)	15.4 (14.4-16.3)	16.6 (15.5-17.7)	17.9 (16.7-19.0)	19.5 (18.1-20.9)	20.8 (19.3-22.3)
45-day	10.4 (9.89-11.0)	12.2 (11.6-12.9)	14.0 (13.3-14.8)	15.4 (14.6-16.2)	17.2 (16.3-18.1)	18.6 (17.5-19.6)	19.9 (18.7-21.0)	21.2 (19.9-22.5)	23.0 (21.5-24.4)	24.3 (22.7-25.8)
60-day	12.5 (11.9-13.1)	14.6 (13.9-15.4)	16.6 (15.7-17.4)	18.1 (17.1-19.0)	20.0 (19.0-21.1)	21.5 (20.3-22.6)	22.9 (21.6-24.1)	24.2 (22.9-25.6)	26.0 (24.5-27.5)	27.4 (25.7-29.0)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS).

Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values.





Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical

PDS-based depth-duration-frequency (DDF) curves



Latitude: 35.9053°, Longitude: -78.4520°




NOAA Atlas 14, Volume 2, Version 3

Created (GMT): Wed Jun 3 19:09:38 2020

[Back to Top](#)**Maps & arials****Small scale terrain**

**Large scale terrain****Large scale map****Large scale aerial**



[Back to Top](#)

[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)

*PRE-DEVELOPMENT
HYDROLOGIC CALCULATIONS*

PRE-DEVELOPMENT HYDROLOGY
Subbasin 1

Land Use	HSG	CN	Onsite	Percent Impervious (%)	Impervious Area (ac)	Total Area (ac)
Crops	B	78	Yes	0	0.00	23.79
Crops	B/D	89	Yes	0	0.00	0.13
Crops	D	89	Yes	0	0.00	6.70
Low Density Residential	B	68		20	0.06	0.29
Low Density Residential	D	84		20	4.53	22.63
Medium Density Residential	B	70		25	0.29	1.14
Medium Density Residential	D	85		25	0.02	0.08
Mixed Use Neighborhood	B	85		65	9.26	14.25
Mixed Use Neighborhood	B/D	92		65	2.68	4.12
Mixed Use Neighborhood	C	90		65	1.16	1.79
Mixed Use Neighborhood	D	92		65	10.60	16.30
Open	B	61	Yes	0	0.00	16.63
Open	B/D	80	Yes	0	0.00	0.38
Open	D	80	Yes	0	0.00	8.88
Pond	B	100	Yes	0	0.00	0.13
Pond	B/D	100	Yes	0	0.00	0.02
Pond	D	100	Yes	0	0.00	6.78
Roadway		98		100	7.98	7.98
Roof	B	98	Yes	100	0.35	0.35
Roof	D	98	Yes	100	0.00	0.00
School	B	88		72	12.90	17.91
School	B/D	93		72	6.11	8.49
School	D	93		72	43.84	60.89
Trail	B	82	Yes	100	0.52	0.52
Trail	B/D	89	Yes	100	0.01	0.01
Trail	D	89	Yes	100	0.11	0.11
Wooded	B	55	Yes	0	0.00	8.52
Wooded	B/D	77	Yes	0	0.00	6.40
Wooded	C	70	Yes	0	0.00	0.03
Wooded	D	77	Yes	0	0.00	1.61

Total Area	236.88 ac
Total Impervious Area	100.42 ac
Onsite Area	81.00 ac
Onsite Impervious Area	0.99 ac
Percent Impervious	42 %
Composite Curve Number	89

Time of Concentration Information

Time of concentration is calculated using the SCS Segmental Approach (TR-55).

Segment 1: Overland Flow

Length = 100 ft
Top Elev = 426.00 ft
Bot Elev = 425.00 ft
Height = 1 ft
Slope = 0.0100 ft/ft
Manning's n = 0.17 cultivated soils, residue cover
P (2-year/24-hour) = 3.46 inches (Rolesville, NC)
Segment Time = 13.74 minutes

Segment 2: Concentrated Flow

Length = 2645 ft
Top Elev = 425.00 ft
Bot Elev = 374.00 ft
Height = 51 ft
Slope = 0.0193 ft/ft
Paved ? = No
Velocity = 2.24 ft/sec
Segment Time = 19.68 minutes

Segment 3: Open Water Flow

Length = 580 ft
Top Elev = 374.00 ft
Bot Elev = 372.00 ft
Segment Time = 0.00 minutes

Segment 4: Channel Flow

Length = 2088 ft
Top Elev = 372.00 ft
Bot Elev = 344.00 ft
Height = 28 ft
Slope = 0.0134 ft/ft
Manning's n = 0.045 natural channel
Flow Area = 15.00 sf (assume 5'w x 3'h channel)
Wetted Perimeter = 11.00 lf (assume 5'w x 3'h channel)
Channel Velocity = 4.72 ft/sec
Segment Time = 7.38 minutes

Time of Concentration =	40.80	minutes
SCS Lag Time =	24.48	minutes (SCS Lag = 0.6* Tc)
Time Increment =	7.10	minutes (= 0.29*SCS Lag)

Land Use	HSG	CN	Onsite	Percent Impervious (%)	Impervious Area (ac)	Area (ac)
Crops	B	78	Yes	0	0.00	1.34
Crops	D	89	Yes	0	0.00	0.55
Low Density Residential	D	84		20	3.59	17.96
Mixed Use Neighborhood	B	85		65	3.44	5.30
Mixed Use Neighborhood	B/D	92		65	0.58	0.89
Mixed Use Neighborhood	D	92		65	8.11	12.48
Open	B	61	Yes	0	0.00	0.92
Open	D	80	Yes	0	0.00	0.75
Roadway		98		100	13.35	13.35
Trail	B	82	Yes	100	0.07	0.07
Trail	D	89	Yes	100	0.22	0.22
Wooded	B	55	Yes	0	0.00	2.53
Wooded	B/D	77	Yes	0	0.00	1.21
Wooded	D	77	Yes	0	0.00	2.33

Total Area	59.90 ac
Total Impervious Area	29.36 ac
Onsite Area	9.92 ac
Onsite Impervious Area	0.28 ac
Percent Impervious	49 %
Composite Curve Number	87

Time of Concentration Information

Time of concentration is calculated using the SCS Segmental Approach (TR-55).

Segment 1: Overland Flow

Length =	100	ft
Top Elev =	427.00	ft
Bot Elev =	426.00	ft
Height =	1	ft
Slope =	0.0100	ft/ft
Manning's n =	0.17	cultivated soils, residue cover
P (2-year/24-hour) =	3.46	inches (Rolesville, NC)
Segment Time =	13.74	minutes

Segment 2: Concentrated Flow

Length =	2541	ft
Top Elev =	426.00	ft
Bot Elev =	368.00	ft
Height =	58	ft
Slope =	0.0228	ft/ft
Paved ? =	No	
Velocity =	2.44	ft/sec
Segment Time =	17.37	minutes

Time of Concentration =	31.12	minutes
SCS Lag Time =	18.67	minutes (SCS Lag = 0.6* Tc)
Time Increment =	5.41	minutes (= 0.29*SCS Lag)

Land Use	HSG	CN	Onsite	Percent Impervious (%)	Impervious Area (ac)	Area (ac)
Open	C	74	Yes	0	0.00	1.23
Open	D	80	Yes	0	0.00	1.45
Wooded	C	70	Yes	0	0.00	0.85
Wooded	D	77	Yes	0	0.00	4.59

Total Area	8.11 ac
Total Impervious Area	0.00 ac
Onsite Area	8.11 ac
Onsite Impervious Area	0.00 ac
Percent Impervious	0 %
Composite Curve Number	76

Time of Concentration Information

Time of concentration is calculated using the SCS Segmental Approach (TR-55).

Segment 1: Overland Flow

Length =	100	ft
Top Elev =	368.00	ft
Bot Elev =	363.00	ft
Height =	5	ft
Slope =	0.0500	ft/ft
Manning's n =	0.24	dense grasses
P (2-year/24-hour) =	3.46	inches (Rolesville, NC)
Segment Time =	9.51	minutes

Segment 2: Concentrated Flow

Length =	881	ft
Top Elev =	363.00	ft
Bot Elev =	336.00	ft
Height =	27	ft
Slope =	0.0306	ft/ft
Paved ? =	No	
Velocity =	2.82	ft/sec
Segment Time =	5.20	minutes

Segment 3: Channel Flow

Length =	249	ft
Top Elev =	336.00	ft
Bot Elev =	333.00	ft
Height =	3	ft
Slope =	0.0120	ft/ft
Manning's n =	0.045	natural channel
Flow Area =	15.00	sf (assume 5'w x 3'h channel)
Wetted Perimeter =	11.00	lf (assume 5'w x 3'h channel)
Channel Velocity =	4.47	ft/sec
Segment Time =	0.93	minutes

Time of Concentration =	15.64	minutes
SCS Lag Time =	9.38	minutes (SCS Lag = 0.6* Tc)
Time Increment =	2.72	minutes (= 0.29*SCS Lag)

PRE-DEVELOPMENT HYDROLOGY
Subbasin 4

Land Use	HSG	CN	Onsite	Percent Impervious (%)	Impervious Area (ac)	Area (ac)
Crops	B	78	Yes	0	0.00	6.35
Crops	B/D	89	Yes	0	0.00	0.16
Crops	D	89	Yes	0	0.00	3.19
Mixed Use Neighborhood	B	85		65	1.18	1.82
Mixed Use Neighborhood	B/D	92		65	0.56	0.86
Mixed Use Neighborhood	C	90		65	0.68	1.04
Mixed Use Neighborhood	D	92		65	5.08	7.81
Open	A	39	Yes	0	0.00	1.44
Open	B	61	Yes	0	0.00	10.63
Open	B/D	80	Yes	0	0.00	8.78
Open	C	74	Yes	0	0.00	4.91
Open	D	80	Yes	0	0.00	20.40
Roadway		98		100	7.47	7.47
Roof	B	98	Yes	100	0.11	0.11
Roof	B/D	98	Yes	100	0.00	0.00
Roof	D	98	Yes	100	0.03	0.03
Trail	A	72	Yes	100	0.17	0.17
Trail	B	82	Yes	100	0.39	0.39
Trail	B/D	89	Yes	100	0.19	0.19
Trail	D	89	Yes	100	0.69	0.69
Wooded	A	30	Yes	0	0.00	0.00
Wooded	B	55	Yes	0	0.00	3.07
Wooded	B/D	77	Yes	0	0.00	9.47
Wooded	C	70	Yes	0	0.00	7.15
Wooded	D	77	Yes	0	0.00	12.43

Total Area	108.57 ac
Total Impervious Area	16.56 ac
Onsite Area	89.56 ac
Onsite Impervious Area	1.59 ac
Percent Impervious	15 %
Composite Curve Number	78

Time of Concentration Information

Time of concentration is calculated using the SCS Segmental Approach (TR-55).

Segment 1: Overland Flow

Length = 100 ft
Top Elev = 389.00 ft
Bot Elev = 388.00 ft
Height = 1 ft
Slope = 0.0100 ft/ft
Manning's n = 0.17 cultivated soils, residue cover
P (2-year/24-hour) = 3.46 inches (Rolesville, NC)
Segment Time = 13.74 minutes

Segment 2: Concentrated Flow

Length = 1855 ft
Top Elev = 388.00 ft
Bot Elev = 339.00 ft
Height = 49 ft
Slope = 0.0264 ft/ft
Paved ? = No
Velocity = 2.62 ft/sec
Segment Time = 11.79 minutes

Segment 3: Channel Flow

Length = 2366 ft
Top Elev = 339.00 ft
Bot Elev = 302.00 ft
Height = 37 ft
Slope = 0.0156 ft/ft
Manning's n = 0.045 natural channel
Flow Area = 15.00 sf (assume 5'w x 3'h channel)
Wetted Perimeter = 11.00 lf (assume 5'w x 3'h channel)
Channel Velocity = 5.09 ft/sec
Segment Time = 7.74 minutes

Time of Concentration =	33.28	minutes
SCS Lag Time =	19.97	minutes (SCS Lag = 0.6* Tc)
Time Increment =	5.79	minutes (= 0.29*SCS Lag)

PRE-DEVELOPMENT HYDROLOGY
Subbasin 5

Land Use	HSG	CN	Onsite	Percent Impervious (%)	Impervious Area (ac)	Area (ac)
Business Park	A	89		85	0.01	0.01
Business Park	B	92		85	0.02	0.02
Business Park	D	95		85	0.03	0.03
Commercial	D	95		85	0.86	1.01
High Density Residential	B	85		65	46.03	70.82
High Density Residential	D	92		65	33.44	51.45
Low Density Residential	B	65		20	0.18	0.92
Low Density Residential	D	82		20	0.37	1.85
Medium Density Residential	A	54		25	0.00	0.01
Medium Density Residential	B	70		25	11.98	47.92
Medium Density Residential	D	85		25	10.74	42.98
Mixed Use Neighborhood	B	85		65	4.36	6.71
Mixed Use Neighborhood	B/D	92		65	2.15	3.31
Mixed Use Neighborhood	D	92		65	7.50	11.55
Open	A	49	Yes	0	0.00	1.90
Open	B	69	Yes	0	0.00	10.33
Open	D	84	Yes	0	0.00	11.86
Preserved Open Space	A	39		0	0.00	0.39
Preserved Open Space	B	61		0	0.00	4.48
Preserved Open Space	D	80		0	0.00	34.05
Roadway		98		100	49.05	49.05
School	B	88		72	0.34	0.47
School	D	93		72	5.12	7.11
Town Center	B	92		85	5.55	6.53
Town Center	D	95		85	1.48	1.74
Trail	A	72	Yes	100	0.02	0.02
Trail	B	82	Yes	100	0.43	0.43
Trail	D	89	Yes	100	1.93	1.93
Wooded	A	30	Yes	0	0.00	0.70
Wooded	B	55	Yes	0	0.00	4.50
Wooded	B/D	77	Yes	0	0.00	0.15
Wooded	D	77	Yes	0	0.00	50.68
Total Area	424.89 ac					
Total Impervious Area	181.60 ac					
Onsite Area	82.49 ac					
Onsite Impervious Area	2.38 ac					
Percent Impervious	43 %					
Composite Curve Number	84					

Time of Concentration Information

Time of concentration is calculated using the SCS Segmental Approach (TR-55).

Segment 1: Overland Flow

Length = 100 ft
Top Elev = 440.00 ft
Bot Elev = 438.00 ft
Height = 2 ft
Slope = 0.0200 ft/ft
Manning's n = 0.24 dense grasses
P (2-year/24-hour) = 3.46 inches (Rolesville, NC)
Segment Time = 13.72 minutes

Segment 2: Concentrated Flow

Length = 2989 ft
Top Elev = 438.00 ft
Bot Elev = 372.00 ft
Height = 66 ft
Slope = 0.0221 ft/ft
Paved ? = No
Velocity = 2.40 ft/sec
Segment Time = 20.78 minutes

Segment 3: Open Water Flow

Length = 655 ft
Top Elev = 372.00 ft
Bot Elev = 372.00 ft
Segment Time = 0.00 minutes

Segment 4: Concentrated Flow

Length = 2379 ft
Top Elev = 372.00 ft
Bot Elev = 320.00 ft
Height = 52 ft
Slope = 0.0219 ft/ft
Paved ? = No
Velocity = 2.39 ft/sec
Segment Time = 16.62 minutes

Segment 5: Channel Flow

Length = 3730 ft
Top Elev = 320.00 ft
Bot Elev = 292.00 ft
Height = 28 ft
Slope = 0.0075 ft/ft
Manning's n = 0.045 natural channel
Flow Area = 32.00 sf (assume 8'w x 4'h channel)
Wetted Perimeter = 16.00 lf (assume 8'w x 4'h channel)
Channel Velocity = 4.55 ft/sec
Segment Time = 13.65 minutes

Time of Concentration =	48.15	minutes
SCS Lag Time =	28.89	minutes (SCS Lag = 0.6* Tc)
Time Increment =	8.38	minutes (= 0.29*SCS Lag)

Land Use	HSG	CN	Onsite	Percent Impervious (%)	Impervious Area (ac)	Area (ac)
Trail	D	89	Yes	100	0.16	0.16
Wooded	A	30	Yes	0	0.00	0.37
Wooded	D	77	Yes	0	0.00	8.04

Total Area	8.56 ac
Total Impervious Area	0.16 ac
Onsite Area	8.56 ac
Onsite Impervious Area	0.16 ac
Percent Impervious	2 %
Composite Curve Number	75

Time of Concentration Information

Time of concentration is calculated using the SCS Segmental Approach (TR-55).

Segment 1: Overland Flow

Length =	100	ft
Top Elev =	386.00	ft
Bot Elev =	380.00	ft
Height =	6	ft
Slope =	0.0600	ft/ft
Manning's n =	0.40	wooded
P (2-year/24-hour) =	3.46	inches (Rolesville, NC)
Segment Time =	13.31	minutes

Segment 2: Concentrated Flow

Length =	599	ft
Top Elev =	380.00	ft
Bot Elev =	288.00	ft
Height =	92	ft
Slope =	0.1536	ft/ft
Paved ? =	No	
Velocity =	6.32	ft/sec
Segment Time =	1.58	minutes

Time of Concentration =	14.89	minutes
SCS Lag Time =	8.93	minutes (SCS Lag = 0.6* Tc)
Time Increment =	2.59	minutes (= 0.29*SCS Lag)

Land Use	HSG	CN	Onsite	Percent Impervious (%)	Impervious Area (ac)	Area (ac)
Open	A	39	Yes	0	0.00	0.70
Open	B	61	Yes	0	0.00	1.00
Open	D	80	Yes	0	0.00	0.06
Trail	B	82	Yes	100	0.15	0.15
Wooded	A	30	Yes	0	0.00	0.66
Wooded	B	55	Yes	0	0.00	7.85
Wooded	D	77	Yes	0	0.00	5.24

Total Area	15.67 ac
Total Impervious Area	0.15 ac
Onsite Area	15.67 ac
Onsite Impervious Area	0.15 ac
Percent Impervious	1 %
Composite Curve Number	61

Time of Concentration Information

Time of concentration is calculated using the SCS Segmental Approach (TR-55).

Segment 1: Overland Flow

Length =	100	ft
Top Elev =	418.00	ft
Bot Elev =	417.00	ft
Height =	1	ft
Slope =	0.0100	ft/ft
Manning's n =	0.24	dense grasses
P (2-year/24-hour) =	3.46	inches (Rolesville, NC)
Segment Time =	18.11	minutes

Segment 2: Concentrated Flow

Length =	591	ft
Top Elev =	417.00	ft
Bot Elev =	338.00	ft
Height =	79	ft
Slope =	0.1337	ft/ft
Paved ? =	No	
Velocity =	5.90	ft/sec
Segment Time =	1.67	minutes

Segment 3: Channel Flow

Length =	285	ft
Top Elev =	338.00	ft
Bot Elev =	324.00	ft
Height =	14	ft
Slope =	0.0491	ft/ft
Manning's n =	0.045	natural channel
Flow Area =	10.00	sf (assume 5'w x 2'h channel)
Wetted Perimeter =	9.00	lf (assume 5'w x 2'h channel)
Channel Velocity =	7.87	ft/sec
Segment Time =	0.60	minutes

Time of Concentration =	20.38	minutes
SCS Lag Time =	12.23	minutes (SCS Lag = 0.6* Tc)
Time Increment =	3.55	minutes (= 0.29*SCS Lag)

Land Use	HSG	CN	Onsite	Percent Impervious (%)	Impervious Area (ac)	Area (ac)
Open	A	39	Yes	0	0.00	0.67
Open	B	61	Yes	0	0.00	1.24
Open	D	80	Yes	0	0.00	0.02
Trail	A	72	Yes	100	0.04	0.04
Trail	B	82	Yes	100	0.07	0.07
Wooded	A	30	Yes	0	0.00	0.71
Wooded	B	55	Yes	0	0.00	3.22
Wooded	D	77	Yes	0	0.00	0.26

Total Area	6.23 ac
Total Impervious Area	0.11 ac
Onsite Area	6.23 ac
Onsite Impervious Area	0.11 ac
Percent Impervious	2 %
Composite Curve Number	53

Time of Concentration Information

Time of concentration is calculated using the SCS Segmental Approach (TR-55).

Segment 1: Overland Flow


Length =	100	ft
Top Elev =	398.00	ft
Bot Elev =	393.00	ft
Height =	5	ft
Slope =	0.0500	ft/ft
Manning's n =	0.24	dense grasses
P (2-year/24-hour) =	3.46	inches (Rolesville, NC)
Segment Time =	9.51	minutes

Segment 2: Concentrated Flow

Length =	697	ft
Top Elev =	393.00	ft
Bot Elev =	365.00	ft
Height =	28	ft
Slope =	0.0402	ft/ft
Paved ? =	No	
Velocity =	3.23	ft/sec
Segment Time =	3.59	minutes

Time of Concentration =	13.10	minutes
SCS Lag Time =	7.86	minutes (SCS Lag = 0.6* Tc)
Time Increment =	2.28	minutes (= 0.29*SCS Lag)

**Scenario: Pre-
Development**





**FlexTable: Catchment
Table (AWH20000.ppc)**

Current Time: 0.00 min


Notes	Label	Area (User Defined) (acres)	SCS CN	Time of Concentration (min)
PRE	SUB 1	236.88	89.0	40.80
PRE	SUB 2	59.90	87.0	31.12
PRE	SUB 3	8.11	76.0	15.64
PRE	SUB 4	108.57	78.0	33.28
PRE	SUB 5	424.89	84.0	48.15
PRE	SUB 6	8.56	75.0	14.89
PRE	SUB 7	15.67	61.0	20.38
PRE	SUB 8	6.23	53.0	13.10

Catchments Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (min)	Peak Flow (ft ³ /s)
SUB 1	Pre-Dev 1 yr	1	34.657	745.00	283.5
SUB 1	Pre-Dev 10 yr	10	74.868	745.00	545.3
SUB 2	Pre-Dev 1 yr	1	8.007	739.00	77.3
SUB 2	Pre-Dev 10 yr	10	17.950	738.00	153.0
SUB 5	Pre-Dev 1 yr	1	48.954	751.00	359.7
SUB 5	Pre-Dev 10 yr	10	116.278	751.00	787.2
SUB 4	Pre-Dev 1 yr	1	9.218	741.00	80.9
SUB 4	Pre-Dev 10 yr	10	24.755	741.00	204.9
SUB 7	Pre-Dev 1 yr	1	0.405	737.00	2.4
SUB 7	Pre-Dev 10 yr	10	1.820	733.00	17.2
SUB 8	Pre-Dev 1 yr	1	0.061	754.00	0.2
SUB 8	Pre-Dev 10 yr	10	0.458	729.00	4.3
SUB 6	Pre-Dev 1 yr	1	0.618	729.00	8.3
SUB 6	Pre-Dev 10 yr	10	1.774	728.00	22.0
SUB 3	Pre-Dev 1 yr	1	0.620	730.00	8.2
SUB 3	Pre-Dev 10 yr	10	1.739	728.00	21.2

Node Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (min)	Peak Flow (ft ³ /s)
POA 1	Pre-Dev 1 yr	1	34.657	745.00	283.5
POA 1	Pre-Dev 10 yr	10	74.868	745.00	545.3
POA 3	Pre-Dev 1 yr	1	0.620	730.00	8.2
POA 3	Pre-Dev 10 yr	10	1.739	728.00	21.2
POA 4	Pre-Dev 1 yr	1	9.218	741.00	80.9
POA 4	Pre-Dev 10 yr	10	24.755	741.00	204.9
POA 5	Pre-Dev 1 yr	1	48.954	751.00	359.7
POA 5	Pre-Dev 10 yr	10	116.278	751.00	787.2
POA 6	Pre-Dev 1 yr	1	0.618	729.00	8.3
POA 6	Pre-Dev 10 yr	10	1.774	728.00	22.0
POA 7	Pre-Dev 1 yr	1	0.405	737.00	2.4
POA 7	Pre-Dev 10 yr	10	1.820	733.00	17.2
POA 8	Pre-Dev 1 yr	1	0.061	754.00	0.2
POA 8	Pre-Dev 10 yr	10	0.458	729.00	4.3
POA 2	Pre-Dev 1 yr	1	8.007	739.00	77.3
POA 2	Pre-Dev 10 yr	10	17.950	738.00	153.0



McAdams

The John R. McAdams Company, Inc.
2905 Meridian Parkway
Durham, NC 27713

phone 919. 361. 5000
fax 919. 361. 2269

license number: C-0293, C-187

www.mcadamsco.com

CLIENT

ASHTON WOODS
5711 SIX FORKS ROAD, SUITE 300
RALEIGH, NORTH CAROLINA 27609



ASHTON WOODS.

THE POINT
PHASES 1-10 AND 14
PRELIMINARY PLAT PLANS
EAST YOUNG STREET
TOWN OF ROLESVILLE, WAKE FOREST TOWNSHIP,
WAKE COUNTY, NORTH CAROLINA

REVISIONS

NO.	DATE	REV	PER	TOWN	COMMENTS
1	04.09.2020				REV PER TOWN COMMENTS


PLAN INFORMATION

PROJECT NO.	AWH-20000
FILENAME	AWH-20000 PRE
CHECKED BY	DCW
DRAWN BY	LK
SCALE	1" = 450'
DATE	06.19.2020

SHEET

PRE DEVELOPMENT
HYDROLOGY MAP

PRE



*POST-DEVELOPMENT
HYDROLOGIC CALCULATIONS*

POST-DEVELOPMENT HYDROLOGY
Subbasin Sub 1 to SCM A

I. ONSITE SCS CURVE NUMBERS - LAND COVER

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

II. ONSITE SCS CURVE NUMBERS - LOTS

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

BasinID: 0

III. OFFSITE SCS CURVE NUMBERS - ZONING

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

IV. ONSITE AREAS - LAND COVER

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	0	0	0	0	0	0
B	90833	0	86247	24577	11367	4630
B/D	0	0	0	0	0	0
C	0	0	0	0	0	0
D	72662	0	26709	8971	0	9

V. ONSITE AREAS - LOTS

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	0	0
B	0	0	84208	0	23114
B/D	0	0	0	0	0
C	0	0	0	0	0
D	0	0	6862	0	0

VI. OFFSITE AREAS - ZONING

	90% impervious	30% impervious	25% impervious	20% impervious	85% impervious	65% impervious	85% impervious	0% impervious	85% impervious	72% impervious
HSG	Right of Way	High Density Residential	Medium Density Residential	Low Density Residential	Commercial	Mixed Use Neighborhood	Business Park	Preserved Open Space	Town Center	School
A	0	0	0	0	0	0	0	0	0	0
B	0	0	0	0	0	0	0	0	0	0
B/D	0	0	0	0	0	0	0	0	0	0
C	0	0	0	0	0	0	0	0	0	0
D	186	0	0	0	0	78952	0	0	0	0

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	0	0	0	0
SingleFamily39	0	0	0	0
SingleFamily40	56,464	39,525	5,646	11,293
SingleFamily50	0	0	0	0
SingleFamily60	11,557	8,090	1,156	2,311
Totals	68,021	47,614	6,802	13,604

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc =	11.92	acres
	519328	sf
Composite SCS CN =	85	
Total Impervious Area =	266011	sf
% Impervious =	51.2%	

IX. TIME OF CONCENTRATION

Time of concentration is assumed to be 5 minutes.

Time of Concentration =	5.00	minutes
SCS Lag Time =	3.00	minutes (SCS Lag = 0.6* Tc)
Time Increment =	0.87	minutes (= 0.29* SCS Lag)

POST-DEVELOPMENT HYDROLOGY
Subbasin Sub 1 to SCM B

I. ONSITE SCS CURVE NUMBERS - LAND COVER

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

II. ONSITE SCS CURVE NUMBERS - LOTS

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

III. OFFSITE SCS CURVE NUMBERS - ZONING

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

IV. ONSITE AREAS - LAND COVER

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	0	0	0	0	0	0
B	71700	0	28982	8643	5484	0
B/D	0	0	0	0	0	0
C	0	0	0	0	0	0
D	58586	0	39271	10383	3169	0

V. ONSITE AREAS - LOTS

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	0	0
B	67910	0	0	0	0
B/D	0	0	0	0	0
C	0	0	0	0	0
D	66566	0	0	0	0

VI. OFFSITE AREAS - ZONING

	90% impervious	30% impervious	25% impervious	20% impervious	85% impervious	65% impervious	85% impervious	0% impervious	85% impervious	72% impervious
HSG	Right of Way	High Density Residential	Medium Density Residential	Low Density Residential	Commercial	Mixed Use Neighborhood	Business Park	Preserved Open Space	Town Center	School
A	0	0	0	0	0	0	0	0	0	0
B	1697	0	0	0	0	70164	0	0	0	0
B/D	0	0	0	0	0	0	0	0	0	0
C	0	0	0	0	0	0	0	0	0	0
D	559	0	0	0	0	13932	0	0	0	0

BasinID: 15

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	122,251	85,576	12,225	24,450
SingleFamily39	0	0	0	0
SingleFamily40	0	0	0	0
SingleFamily50	0	0	0	0
SingleFamily60	0	0	0	0
Totals	122,251	85,576	12,225	24,450

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc =	10.26	acres
	447048	sf
Composite SCS CN =	87	
Total Impervious Area =	266224	sf
% Impervious =	59.6%	

IX. TIME OF CONCENTRATION

Time of concentration is assumed to be 5 minutes.

Time of Concentration =	5.00	minutes
SCS Lag Time =	3.00	minutes (SCS Lag = 0.6* Tc)
Time Increment =	0.87	minutes (= 0.29* SCS Lag)

I. ONSITE SCS CURVE NUMBERS - LAND COVER

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

II. ONSITE SCS CURVE NUMBERS - LOTS

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

III. OFFSITE SCS CURVE NUMBERS - ZONING

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

IV. ONSITE AREAS - LAND COVER

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	0	0	0	0	0	0
B	61769	0	73235	21972	1330	804
B/D	0	0	0	0	0	0
C	0	0	0	0	0	0
D	51459	0	40559	12919	13788	88

V. ONSITE AREAS - LOTS

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	0	0
B	0	90183	141800	0	43514
B/D	0	0	0	0	0
C	0	0	0	0	0
D	0	79639	39449	0	10628

VI. OFFSITE AREAS - ZONING

	90% impervious	30% impervious	25% impervious	20% impervious	85% impervious	65% impervious	85% impervious	0% impervious	85% impervious	72% impervious
HSG	Right of Way	High Density Residential	Medium Density Residential	Low Density Residential	Commercial	Mixed Use Neighborhood	Business Park	Preserved Open Space	Town Center	School
A	0	0	0	0	0	0	0	0	0	0
B	0	0	0	0	0	0	0	0	0	0
B/D	0	0	0	0	0	0	0	0	0	0
C	0	0	0	0	0	0	0	0	0	0
D	0	0	0	0	0	0	0	0	0	0

BasinID: 14

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	0	0	0	0
SingleFamily39	109,806	76,864	10,981	21,961
SingleFamily40	112,374	78,662	11,237	22,475
SingleFamily50	0	0	0	0
SingleFamily60	27,071	18,950	2,707	5,414
Totals	249,251	174,476	24,925	49,850

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc =	15.68	acres
	683134	sf
Composite SCS CN =	86	
Total Impervious Area =	397936	sf
% Impervious =	58.3%	

IX. TIME OF CONCENTRATION

Time of concentration is assumed to be 5 minutes.

Time of Concentration =	5.00	minutes
SCS Lag Time =	3.00	minutes (SCS Lag = 0.6* Tc)
Time Increment =	0.87	minutes (= 0.29* SCS Lag)

T. DABOLT
8/2/2021

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

13

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	0	0	0	0	0	0
B	45141	0	59630	16037	8728	1677
B/D	5822	0	3836	1966	0	0
C	0	0	0	0	0	0
D	45560	0	60659	16233	15434	3379

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	0	0
B	0	57697	98197	0	86974
B/D	0	0	1650	0	22691
C	0	0	0	0	0
D	0	49507	101286	0	55579

[illegible]

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	0	0	0	0
SingleFamily39	69,318	48,523	6,932	13,864
SingleFamily40	124,702	87,292	12,470	24,940
SingleFamily50	0	0	0	0
SingleFamily60	82,622	57,836	8,262	16,524
Totals	276,643	193,650	27,664	55,329

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc =	17.39	acres
	757683	sf
Composite SCS CN =	87	
Total Impervious Area =	435004	sf
% Impervious =	57.4%	

IX. TIME OF CONCENTRATION

Time of concentration is assumed to be 5 minutes.

Time of Concentration =	5.00	minutes
SCS Lag Time =	3.00	minutes (SCS Lag = 0.6* Tc)
Time Increment =	0.87	minutes (= 0.29* SCS Lag)

T. DABOLT
8/2/2021

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

16

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	0	0	0	0	0	0
B	70779	0	71986	24952	19528	0
B/D	3050	0	2654	905	85	0
C	0	0	0	0	0	0
D	487	0	383	379	0	0

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	0	0
B	0	0	0	0	362575
B/D	0	0	0	0	17129
C	0	0	0	0	0
D	0	0	0	0	13

[illegible]

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	0	0	0	0
SingleFamily39	0	0	0	0
SingleFamily40	0	0	0	0
SingleFamily50	0	0	0	0
SingleFamily60	189,859	132,901	18,986	37,972
Totals	189,859	132,901	18,986	37,972

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc =	13.20	acres
	574905	sf
Composite SCS CN =	81	
Total Impervious Area =	291118	sf
% Impervious =	50.6%	

IX. TIME OF CONCENTRATION

Time of concentration is assumed to be 5 minutes.

Time of Concentration =	5.00	minutes
SCS Lag Time =	3.00	minutes (SCS Lag = 0.6* Tc)
Time Increment =	0.87	minutes (= 0.29*SCS Lag)

POST-DEVELOPMENT HYDROLOGY
Subbasin Sub 4 to SCM F

I. ONSITE SCS CURVE NUMBERS - LAND COVER

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

II. ONSITE SCS CURVE NUMBERS - LOTS

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

III. OFFSITE SCS CURVE NUMBERS - ZONING

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

IV. ONSITE AREAS - LAND COVER

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	0	0	0	0	0	0
B	53424	0	51366	13332	0	4318
B/D	116287	0	34711	12924	47	0
C	0	0	0	0	0	0
D	65895	0	40542	13681	16065	0

V. ONSITE AREAS - LOTS

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	0	0
B	10184	90465	85971	0	0
B/D	17316	25633	12370	0	0
C	0	0	0	0	0
D	39125	11973	73531	0	26072

VI. OFFSITE AREAS - ZONING

	90% impervious	30% impervious	25% impervious	20% impervious	85% impervious	65% impervious	85% impervious	0% impervious	85% impervious	72% impervious
HSG	Right of Way	High Density Residential	Medium Density Residential	Low Density Residential	Commercial	Mixed Use Neighborhood	Business Park	Preserved Open Space	Town Center	School
A	0	0	0	0	0	0	0	0	0	0
B	0	0	0	0	0	0	0	0	0	0
B/D	0	0	0	0	0	0	0	0	0	0
C	0	0	0	0	0	0	0	0	0	0
D	0	0	0	0	0	0	0	0	0	0

BasinID: 12

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	60,568	42,398	6,057	12,114
SingleFamily39	82,811	57,968	8,281	16,562
SingleFamily40	106,560	74,592	10,656	21,312
SingleFamily50	0	0	0	0
SingleFamily60	13,036	9,125	1,304	2,607
Totals	262,975	184,083	26,298	52,595

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc =	18.72	acres
	815231	sf
Composite SCS CN =	87	
Total Impervious Area =	429531	sf
% Impervious =	52.7%	

IX. TIME OF CONCENTRATION

Time of concentration is assumed to be 5 minutes.

Time of Concentration =	5.00	minutes
SCS Lag Time =	3.00	minutes (SCS Lag = 0.6* Tc)
Time Increment =	0.87	minutes (= 0.29* SCS Lag)

I. ONSITE SCS CURVE NUMBERS - LAND COVER

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

II. ONSITE SCS CURVE NUMBERS - LOTS

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

III. OFFSITE SCS CURVE NUMBERS - ZONING

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

IV. ONSITE AREAS - LAND COVER

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	0	0	0	0	0	0
B	40011	0	31008	11259	0	0
B/D	20490	0	17445	4418	1288	0
C	0	0	0	0	0	0
D	94972	0	52042	17274	14545	0

V. ONSITE AREAS - LOTS

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	0	0
B	56568	0	0	25474	0
B/D	1586	0	0	6060	0
C	0	0	0	0	0
D	103079	0	0	97575	0

VI. OFFSITE AREAS - ZONING

	90% impervious	30% impervious	25% impervious	20% impervious	85% impervious	65% impervious	85% impervious	0% impervious	85% impervious	72% impervious
HSG	Right of Way	High Density Residential	Medium Density Residential	Low Density Residential	Commercial	Mixed Use Neighborhood	Business Park	Preserved Open Space	Town Center	School
A	0	0	0	0	0	0	0	0	0	0
B	0	0	0	0	0	0	0	0	0	0
B/D	0	0	0	0	0	0	0	0	0	0
C	0	0	0	0	0	0	0	0	0	0
D	0	0	0	0	0	0	0	0	0	0

BasinID: 8

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	146,576	102,603	14,658	29,315
SingleFamily39	0	0	0	0
SingleFamily40	0	0	0	0
SingleFamily50	75,576	52,903	7,558	15,115
SingleFamily60	0	0	0	0
Totals	222,152	155,506	22,215	44,430

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc =	13.66	acres
	595094	sf
Composite SCS CN =	90	
Total Impervious Area =	355598	sf
% Impervious =	59.8%	

IX. TIME OF CONCENTRATION

Time of concentration is assumed to be 5 minutes.

Time of Concentration =	5.00	minutes
SCS Lag Time =	3.00	minutes (SCS Lag = 0.6* Tc)
Time Increment =	0.87	minutes (= 0.29* SCS Lag)

T. DABOLT
8/2/2021

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

6

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	0	0	0	0	0	0
B	0	0	0	0	0	0
B/D	9097	0	12526	3521	0	0
C	41860	73	56870	17719	0	0
D	47299	9384	30675	8063	17405	0

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	0	0
B	0	0	0	0	0
B/D	0	0	0	17962	0
C	0	0	0	336019	0
D	0	0	0	106065	0

[illegible]

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	0	0	0	0
SingleFamily39	0	0	0	0
SingleFamily40	0	0	0	0
SingleFamily50	269,295	188,507	26,930	53,859
SingleFamily60	0	0	0	0
Totals	269,295	188,507	26,930	53,859

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc =	16.40	acres
	714538	sf
Composite SCS CN =	89	
Total Impervious Area =	398669	sf
% Impervious =	55.8%	

IX. TIME OF CONCENTRATION

Time of concentration is assumed to be 5 minutes.

Time of Concentration =	5.00	minutes
SCS Lag Time =	3.00	minutes (SCS Lag = 0.6* Tc)
Time Increment =	0.87	minutes (= 0.29* SCS Lag)

T. DABOLT
8/2/2021

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

7

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	6505	0	11402	4011	0	0
B	1734	0	3686	1333	0	0
B/D	113	0	0	0	0	0
C	0	0	0	0	0	0
D	57013	0	33703	11780	7845	0

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	39602	0
B	0	0	0	30142	0
B/D	0	0	0	0	0
C	0	0	0	0	0
D	0	0	0	155736	0

[illegible]

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	0	0	0	0
SingleFamily39	0	0	0	0
SingleFamily40	0	0	0	0
SingleFamily50	131,988	92,391	13,199	26,398
SingleFamily60	0	0	0	0
Totals	131,988	92,391	13,199	26,398

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc =	8.37	acres
	364606	sf
Composite SCS CN =	87	
Total Impervious Area =	197903	sf
% Impervious =	54.3%	

IX. TIME OF CONCENTRATION

Time of concentration is assumed to be 5 minutes.

Time of Concentration =	5.00	minutes
SCS Lag Time =	3.00	minutes (SCS Lag = 0.6* Tc)
Time Increment =	0.87	minutes (= 0.29*SCS Lag)

T. DABOLT
8/2/2021

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	24271	0	8528	2982	0	0
B	27857	0	18300	5506	0	0
B/D	0	0	0	0	0	0
C	0	0	0	0	0	0
D	95003	64869	58724	17815	13690	0

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	46999	0
B	22302	0	0	18988	0
B/D	0	0	0	0	0
C	0	0	0	0	0
D	25619	0	0	166608	0

[illegible]

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	43,564	30,495	4,356	8,713
SingleFamily39	0	0	0	0
SingleFamily40	0	0	0	0
SingleFamily50	136,153	95,307	13,615	27,231
SingleFamily60	0	0	0	0
Totals	179,718	125,802	17,972	35,944

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc =	14.19	acres
	618061	sf
Composite SCS CN =	85	
Total Impervious Area =	291573	sf
% Impervious =	47.2%	

IX. TIME OF CONCENTRATION

Time of concentration is assumed to be 5 minutes.

Time of Concentration =	5.00	minutes
SCS Lag Time =	3.00	minutes (SCS Lag = 0.6* Tc)
Time Increment =	0.87	minutes (= 0.29* SCS Lag)

I. ONSITE SCS CURVE NUMBERS - LAND COVER

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

II. ONSITE SCS CURVE NUMBERS - LOTS

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

BasinID: 1

III. OFFSITE SCS CURVE NUMBERS - ZONING

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

IV. ONSITE AREAS - LAND COVER

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	0	0	0	0	0	0
B	454874	140808	7655	11691	4131	110741
B/D	38957	238736	0	0	1148	0
C	0	1512	0	0	0	0
D	159038	21927	29	174	295367	8174

V. ONSITE AREAS - LOTS

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	0	0
B	0	0	0	0	13066
B/D	0	0	0	0	0
C	0	0	0	0	0
D	0	0	0	0	2271

VI. OFFSITE AREAS - ZONING

	90% impervious	30% impervious	25% impervious	20% impervious	85% impervious	65% impervious	85% impervious	0% impervious	85% impervious	72% impervious
HSG	Right of Way	High Density Residential	Medium Density Residential	Low Density Residential	Commercial	Mixed Use Neighborhood	Business Park	Preserved Open Space	Town Center	School
A	0	0	0	0	0	0	0	0	0	0
B	178555	0	49735	12823	0	532407	0	0	0	780297
B/D	16957	0	0	0	0	179660	0	0	0	369944
C	0	0	0	0	0	77938	0	0	0	0
D	153068	0	3316	985806	0	617428	0	0	0	2652145

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	0	0	0	0
SingleFamily39	0	0	0	0
SingleFamily40	0	0	0	0
SingleFamily50	0	0	0	0
SingleFamily60	7,668	5,368	767	1,534
Totals	7,668	5,368	767	1,534

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc = 186.42 acres
8120377 sf
 Composite SCS CN = 87
 Total Impervious Area = **4206476** sf
 % Impervious = 51.8%

IX. TIME OF CONCENTRATION

Time of concentration is calculated using the SCS Segmental Approach (TR-55).

Segment 1: Overland Flow

Length = 100 ft
 Top Elev = 426.00 ft
 Bot Elev = 425.00 ft
 Height = 1 ft
 Slope = 0.0100 ft/ft
 Manning's n = 0.17 cultivated soils, residue cover
 P (2-year/24-hour) = 3.46 inches (Rolesville, NC)
Segment Time = 13.74 minutes

Segment 3: Open Water Flow

Length = 580 ft
 Top Elev = 374.00 ft
 Bot Elev = 372.00 ft
Segment Time = 0.00 minutes

Segment 2: Concentrated Flow

Length = 2645 ft
 Top Elev = 425.00 ft
 Bot Elev = 374.00 ft
 Height = 51 ft
 Slope = 0.0193 ft/ft
 Paved ? = No
 Velocity = 2.24 ft/sec
Segment Time = 19.68 minutes

Segment 4: Channel Flow

Length = 2088 ft
 Top Elev = 372.00 ft
 Bot Elev = 344.00 ft
 Height = 28 ft
 Slope = 0.0134 ft/ft
 Manning's n = 0.045 natural channel
 Flow Area = 15.00 sf (assume 5'w x 3'h channel)
 Wetted Perimeter = 11.00 lf (assume 5'w x 3'h channel)
 Channel Velocity = 4.72 ft/sec
Segment Time = 7.38 minutes

Time of Concentration = 40.80 minutes
 SCS Lag Time = 24.48 minutes (SCS Lag = 0.6* Tc)
 Time Increment = 7.10 minutes (= 0.29*SCS Lag)

I. ONSITE SCS CURVE NUMBERS - LAND COVER

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

II. ONSITE SCS CURVE NUMBERS - LOTS

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

III. OFFSITE SCS CURVE NUMBERS - ZONING

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

IV. ONSITE AREAS - LAND COVER

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	0	0	0	0	0	0
B	31858	19412	0	6260	0	22619
B/D	0	52628	0	0	0	0
C	0	0	0	0	0	0
D	22027	23834	0	3127	0	4670

V. ONSITE AREAS - LOTS

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	0	0
B	0	17	0	0	0
B/D	0	0	0	0	0
C	0	0	0	0	0
D	0	0	0	0	0

VI. OFFSITE AREAS - ZONING

	90% impervious	30% impervious	25% impervious	20% impervious	85% impervious	65% impervious	85% impervious	0% impervious	85% impervious	72% impervious
HSG	Right of Way	High Density Residential	Medium Density Residential	Low Density Residential	Commercial	Mixed Use Neighborhood	Business Park	Preserved Open Space	Town Center	School
A	0	0	0	0	0	0	0	0	0	0
B	100879	0	0	0	0	230704	0	0	0	0
B/D	37900	0	0	0	0	38861	0	0	0	0
C	0	0	0	0	0	0	0	0	0	0
D	442930	0	0	782428	0	543504	0	0	0	0

BasinID: 2

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	0	0	0	0
SingleFamily39	11	8	1	2
SingleFamily40	0	0	0	0
SingleFamily50	0	0	0	0
SingleFamily60	0	0	0	0
Totals	11	8	1	2

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc =	54.26	acres
	2363659	sf
Composite SCS CN =	87	
Total Impervious Area =	1217917	sf
% Impervious =	51.5%	

IX. TIME OF CONCENTRATION

Time of concentration is calculated using the SCS Segmental Approach (TR-55).

Segment 1: Overland Flow

Length =	100	ft
Top Elev =	427.00	ft
Bot Elev =	426.00	ft
Height =	1	ft
Slope =	0.0100	ft/ft
Manning's n =	0.17	cultivated soils, residue cover
P (2-year/24-hour) =	3.46	inches (Rolesville, NC)
Segment Time =	13.74	minutes

Segment 2: Concentrated Flow

Length =	2541	ft
Top Elev =	426.00	ft
Bot Elev =	368.00	ft
Height =	58	ft
Slope =	0.0228	ft/ft
Paved ? =	No	
Velocity =	2.44	ft/sec
Segment Time =	17.37	minutes

Time of Concentration =	31.12	minutes
SCS Lag Time =	18.67	minutes (SCS Lag = 0.6* Tc)
Time Increment =	5.41	minutes (= 0.29*SCS Lag)

I. ONSITE SCS CURVE NUMBERS - LAND COVER

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

II. ONSITE SCS CURVE NUMBERS - LOTS

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

III. OFFSITE SCS CURVE NUMBERS - ZONING

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

IV. ONSITE AREAS - LAND COVER

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	0	0	0	0	0	0
B	0	0	0	0	0	0
B/D	0	0	0	0	0	0
C	9831	10071	0	0	0	0
D	33156	180414	0	0	0	0

V. ONSITE AREAS - LOTS

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	0	0
B	0	0	0	0	0
B/D	0	0	0	0	0
C	0	0	0	54	0
D	0	0	0	916	0

VI. OFFSITE AREAS - ZONING

	90% impervious	30% impervious	25% impervious	20% impervious	85% impervious	65% impervious	85% impervious	0% impervious	85% impervious	72% impervious
HSG	Right of Way	High Density Residential	Medium Density Residential	Low Density Residential	Commercial	Mixed Use Neighborhood	Business Park	Preserved Open Space	Town Center	School
A	0	0	0	0	0	0	0	0	0	0
B	0	0	0	0	0	0	0	0	0	0
B/D	0	0	0	0	0	0	0	0	0	0
C	0	0	0	0	0	0	0	0	0	0
D	0	0	0	0	0	0	0	0	0	0

BasinID: 4

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	0	0	0	0
SingleFamily39	0	0	0	0
SingleFamily40	0	0	0	0
SingleFamily50	568	397	57	114
SingleFamily60	0	0	0	0
Totals	568	397	57	114

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc =	5.38	acres
	234442	sf
Composite SCS CN =	77	
Total Impervious Area =	568	sf
% Impervious =	0.2%	

IX. TIME OF CONCENTRATION

Time of concentration is calculated using the SCS Segmental Approach (TR-55).

Segment 1: Overland Flow

Length =	100	ft
Top Elev =	368.00	ft
Bot Elev =	363.00	ft
Height =	5	ft
Slope =	0.0500	ft/ft
Manning's n =	0.24	dense grasses
P (2-year/24-hour) =	3.46	inches (Rolesville, NC)
Segment Time =	9.51	minutes

Segment 3: Channel Flow

Length =	249	ft
Top Elev =	336.00	ft
Bot Elev =	333.00	ft
Height =	3	ft
Slope =	0.0120	ft/ft
Manning's n =	0.045	natural channel
Flow Area =	15.00	sf (assume 5'w x 3'h channel)
Wetted Perimeter =	11.00	lf (assume 5'w x 3'h channel)
Channel Velocity =	4.47	ft/sec
Segment Time =	0.93	minutes

Segment 2: Concentrated Flow

Length =	881	ft
Top Elev =	363.00	ft
Bot Elev =	336.00	ft
Height =	27	ft
Slope =	0.0306	ft/ft
Paved ? =	No	
Velocity =	2.82	ft/sec
Segment Time =	5.20	minutes

Time of Concentration =	15.64	minutes
SCS Lag Time =	9.38	minutes (SCS Lag = 0.6* Tc)
Time Increment =	2.72	minutes (= 0.29*SCS Lag)

I. ONSITE SCS CURVE NUMBERS - LAND COVER

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

II. ONSITE SCS CURVE NUMBERS - LOTS

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

III. OFFSITE SCS CURVE NUMBERS - ZONING

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

IV. ONSITE AREAS - LAND COVER

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	0	0	0	0	0	0
B	0	0	0	0	0	0
B/D	3819	37875	0	0	0	0
C	9443	3612	0	0	0	0
D	19783	16409	0	0	0	0

V. ONSITE AREAS - LOTS

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	0	0
B	0	0	0	0	0
B/D	0	0	0	0	0
C	0	0	0	107	0
D	0	0	0	0	732

VI. OFFSITE AREAS - ZONING

	90% impervious	30% impervious	25% impervious	20% impervious	85% impervious	65% impervious	85% impervious	0% impervious	85% impervious	72% impervious
HSG	Right of Way	High Density Residential	Medium Density Residential	Low Density Residential	Commercial	Mixed Use Neighborhood	Business Park	Preserved Open Space	Town Center	School
A	0	0	0	0	0	0	0	0	0	0
B	0	0	0	0	0	77543	0	0	0	0
B/D	0	0	0	0	0	36707	0	0	0	0
C	0	0	0	0	0	45463	0	0	0	0
D	0	0	0	0	0	311989	0	0	0	0

BasinID: 5

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	0	0	0	0
SingleFamily39	0	0	0	0
SingleFamily40	0	0	0	0
SingleFamily50	63	44	6	13
SingleFamily60	366	256	37	73
Totals	429	300	43	86

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc =	12.94	acres
	563481	sf
Composite SCS CN =	88	
Total Impervious Area =	307035	sf
% Impervious =	54.5%	

IX. TIME OF CONCENTRATION

Time of concentration is calculated using the SCS Segmental Approach (TR-55).

Segment 1: Overland Flow

Length =	100	ft
Top Elev =	389.00	ft
Bot Elev =	388.00	ft
Height =	1	ft
Slope =	0.0100	ft/ft
Manning's n =	0.17	cultivated soils, residue cover
P (2-year/24-hour) =	3.46	inches (Rolesville, NC)
Segment Time =	13.74	minutes

Segment 3: Channel Flow

Length =	2366	ft
Top Elev =	339.00	ft
Bot Elev =	302.00	ft
Height =	37	ft
Slope =	0.0156	ft/ft
Manning's n =	0.045	natural channel
Flow Area =	15.00	sf (assume 5'w x 3'h channel)
Wetted Perimeter =	11.00	lf (assume 5'w x 3'h channel)
Channel Velocity =	5.09	ft/sec
Segment Time =	7.74	minutes

Segment 2: Concentrated Flow

Length =	1855	ft
Top Elev =	388.00	ft
Bot Elev =	339.00	ft
Height =	49	ft
Slope =	0.0264	ft/ft
Paved ? =	No	
Velocity =	2.62	ft/sec
Segment Time =	11.79	minutes

Time of Concentration =	33.28	minutes
SCS Lag Time =	19.97	minutes (SCS Lag = 0.6* Tc)
Time Increment =	5.79	minutes (= 0.29* SCS Lag)

POST-DEVELOPMENT HYDROLOGY
Subbasin Sub 5 BYPASS

I. ONSITE SCS CURVE NUMBERS - LAND COVER

HSG	Open	Wooded	Roads	Sidewalk	Pond	Crops
A	39	30	98	98	100	67
B	61	55	98	98	100	78
B/D	80	77	98	98	100	89
C	74	70	98	98	100	85
D	80	77	98	98	100	89

II. ONSITE SCS CURVE NUMBERS - LOTS

HSG	22' Townhome	39' Single Family	40' Single Family	50' Single Family	60' Single Family
A	93	77	76	74	69
B	95	85	84	83	80
B/D	96	92	91	91	89
C	96	90	89	88	86
D	96	92	91	91	89

III. OFFSITE SCS CURVE NUMBERS - ZONING

HSG	Right-Of-Way	Zoning - High Res (1/3 acre)	Zoning - Med Res (1/2 acre)	Zoning - Low Res (1 acre)	Zoning - Commercial	Zoning - MU Neighborhood	Zoning - Business Park	Zoning - Preserved Open	Town Center	School
A	83	57	54	51	89	72	89	39	89	75
B	89	72	70	68	92	85	92	61	92	88
B/D	93	86	85	84	95	92	95	80	95	93
C	91	82	80	79	94	90	94	74	94	91
D	93	86	85	84	95	92	95	80	95	93

IV. ONSITE AREAS - LAND COVER

HSG	Open	Onsite Wooded	Onsite Roads	Onsite Sidewalk	Pond	Onsite Crops
A	19289	0	0	0	0	0
B	463037	165474	0	11246	0	3659
B/D	27508	6355	0	4062	0	0
C	0	0	0	0	0	0
D	588891	1286887	0	11685	0	0

V. ONSITE AREAS - LOTS

HSG	Townhome22	SingleFamily39	SingleFamily40	SingleFamily50	SingleFamily60
A	0	0	0	0	0
B	0	0	0	0	0
B/D	0	0	0	0	0
C	0	0	0	0	0
D	96	0	0	0	0

VI. OFFSITE AREAS - ZONING

	90% impervious	30% impervious	25% impervious	20% impervious	85% impervious	65% impervious	85% impervious	0% impervious	85% impervious	72% impervious
HSG	Right of Way	High Density Residential	Medium Density Residential	Low Density Residential	Commercial	Mixed Use Neighborhood	Business Park	Preserved Open Space	Town Center	School
A	32917	0	310	0	0	0	272	17137	0	0
B	1041178	3084838	2087277	40019	0	294169	868	195327	284266	20637
B/D	68437	0	0	0	0	145164	0	0	0	0
C	0	0	0	0	0	0	0	0	0	0
D	1328907	2241086	1872118	80782	43820	531367	1360	1483036	75630	309591

BasinID: 11

VII. LOT BREAKDOWN

Contributing Area	Total Impervious [sf]	Roof Area [sf]	Sidewalk Area [sf]	Driveway Area [sf]
Townhome22	87	61	9	17
SingleFamily39	0	0	0	0
SingleFamily40	0	0	0	0
SingleFamily50	0	0	0	0
SingleFamily60	0	0	0	0
Totals	87	61	9	17

VIII. TOTAL DRAINAGE AREA RESULT

Total Area per GIS Calc = 410.21 acres
17868706 sf

Composite SCS CN = 80

Total Impervious Area = 6077244 sf

% Impervious = 34.0%

IX. TIME OF CONCENTRATION

Time of concentration is calculated using the SCS Segmental Approach (TR-55).

Segment 1: Overland Flow

Length = 100 ft
Top Elev = 440.00 ft
Bot Elev = 438.00 ft
Height = 2 ft
Slope = 0.0200 ft/ft
Manning's n = 0.24 dense grasses
P (2-year/24-hour) = 3.46 inches (Rolesville, NC)
Segment Time = 13.72 minutes

Segment 3: Open Water Flow

Length = 655 ft
Top Elev = 372.00 ft
Bot Elev = 372.00 ft
Segment Time = 0.00 minutes

Segment 5: Channel Flow

Length = 3730 ft
Top Elev = 320.00 ft
Bot Elev = 292.00 ft
Height = 28 ft
Slope = 0.0075 ft/ft

Segment 2: Concentrated Flow

Length = 2989 ft
Top Elev = 438.00 ft
Bot Elev = 372.00 ft
Height = 66 ft
Slope = 0.0221 ft/ft
Paved ? = No
Velocity = 2.40 ft/sec
Segment Time = 20.78 minutes

Segment 4: Concentrated Flow

Length = 2379 ft
Top Elev = 372.00 ft
Bot Elev = 320.00 ft
Height = 52 ft
Slope = 0.0219 ft/ft
Paved ? = No
Velocity = 2.39 ft/sec
Segment Time = 16.62 minutes

REACH DATA

Reach 1 - POA 1 to POA 4

Length = 2988 ft
Top Elev = 344.00 ft
Bot Elev = 302.00 ft
Height = 42 ft
Slope = 0.0141 ft/ft
Manning's n = 0.045 natural channel
Flow Area = 10.00 sf (assume 5'w x 2'h channel)
Wetted Perimeter = 9.00 lf (assume 5'w x 2'h channel)
Channel Velocity = 4.21 ft/sec
Reach Travel Time = 11.83 minutes

Reach 2 - SCM A to POA 1

Segment 1: Concentrated Flow

Length = 647 ft
Top Elev = 377.00 ft
Bot Elev = 368.00 ft
Height = 9 ft
Slope = 0.0139 ft/ft
Paved ? = No
Velocity = 1.90 ft/sec

Segment Time = 5.67 minutes

Segment 2: Channel Flow

Length = 2038 ft
Top Elev = 368.00 ft
Bot Elev = 344.00 ft
Height = 24 ft
Slope = 0.0118 ft/ft
Manning's n = 0.045 natural channel
Flow Area = 12.00 sf (assume 6'w x 2'h channel)
Wetted Perimeter = 10.00 lf (assume 6'w x 2'h channel)
Channel Velocity = 4.06 ft/sec
Reach Travel Time = 8.37 minutes

Total Reach Travel Time = 14.04

Reach 3 - SCM C to POA 1

Segment 1: Concentrated Flow

Length = 83 ft
Top Elev = 370.00 ft
Bot Elev = 366.00 ft
Height = 4 ft
Slope = 0.0482 ft/ft
Paved ? = No
Velocity = 3.54 ft/sec

Segment Time = 0.39 minutes

Segment 2: Channel Flow

Length = 1220 ft
Top Elev = 366.00 ft
Bot Elev = 344.00 ft
Height = 22 ft
Slope = 0.0180 ft/ft
Manning's n = 0.045 natural channel
Flow Area = 8.00 sf (assume 4'w x 2'h channel)
Wetted Perimeter = 8.00 lf (assume 4'w x 2'h channel)
Channel Velocity = 4.45 ft/sec
Reach Travel Time = 4.57 minutes

Total Reach Travel Time = 4.96

Reach 4 - SCM F to POA 4

Segment 1: Concentrated Flow

Length = 77 ft
Top Elev = 339.00 ft
Bot Elev = 336.00 ft
Height = 3 ft
Slope = 0.0390 ft/ft
Paved ? = No
Velocity = 3.18 ft/sec

Segment Time = 0.40 minutes

Segment 2: Channel Flow

Length = 2292 ft
Top Elev = 336.00 ft
Bot Elev = 302.00 ft
Height = 34 ft
Slope = 0.0148 ft/ft
Manning's n = 0.045 natural channel
Flow Area = 10.00 sf (assume 5'w x 2'h channel)
Wetted Perimeter = 9.00 lf (assume 5'w x 2'h channel)
Channel Velocity = 4.33 ft/sec
Reach Travel Time = 8.83 minutes

Total Reach Travel Time = 9.23

THE POINTE
AWH20000

POST-DEVELOPMENT HYDROLOGY
Subbasin GIS Output-Onsite

T. DABOLT
8/2/2021

NUTRIENT INPUT SUMMARY

SCM A,B,C,D,E,F,G,H,I,J - Wet Pond

Land Use	Treated Area (sf)	Bypassed Area (sf)
Impervious	3,099,079	80,366
Pond	165,231	301,794
Open	2,757,306	2,207,029
Wooded	74,326	3,023,652
Total	6,095,942	5,612,840

Total Lot Area =	1905531	sf
Total Treated Lot Area =	1890177	sf
Total Untreated Lot Area =	15354	sf
Total Lot Impervious =	1054857	sf
Total Lot Open =	850674	sf

SUB 1 TO SCM A	SUB 1 BYPASS
SUB 1 TO SCM C	SUB 2 BYPASS
SUB 1 TO SCM D	SUB 3 BYPASS
SUB 1 TO SCM E	SUB 4 BYPASS
SUB 4 TO SCM F	SUB 5 BYPASS
SUB 1 TO SCM B	
SUB 4 TO SCM G	
SUB 4 TO SCM H	
SUB 4 TO SCM I	
SUB 5 TO SCM J	

Total Area	15659221 sf
Right of Way	4531152 sf
Nitrogen Area	11128069 sf
Treated+Untreated Total	11708783 sf

TREATED AREA BREAKDOWN											
	ONSITE ROADS	ONSITE SIDEWALK	RIGHT OF WAY	POND	ONSITE WOODED	ONSITE CROPS	OPEN	SINGLEFAMILY39	SINGLEFAMILY40	SINGLEFAMILY60	SINGLEFAM50
SCM A	252621	76067	557	11367	0	4640	326989	0	91070	23114	0
SCM C	227589	69781	0	15117	0	892	174997	260004	181249	54142	0
SCM D	75024	26235	0	19613	0	0	74316	0	0	379717	0
SCM E	124125	50470	0	39596	0	8435	96523	107204	302418	165244	0
SCM F	253238	79872	0	16112	0	17271	235606	128071	171872	26072	0
SCM B	126217	46696	6211	8653	0	0	260572	0	0	0	0
SCM G	152537	50224	0	15833	0	0	155473	0	0	0	129109
SCM H	200143	58605	0	17405	9457	0	98256	0	0	0	460046
SCM I	48791	17124	0	7845	0	0	122379	0	0	0	225479
SCM J	85552	31810	0	13690	64869	0	337136	0	0	0	232595

BYPASSED AREA BREAKDOWN											
	ONSITE ROADS	ONSITE SIDEWALK	RIGHT OF WAY	POND	ONSITE WOODED	ONSITE CROPS	OPEN	ONSITE TRAIL	SINGLEFAMILY39	SINGLEFAMILY40	SINGLEFAMILY60
SUB 1 BYPASS	15367	47112	1028781	301794	543791	229656	1760613	0	0	0	15337
SUB 2 BYPASS	0	9387	1125518	0	191748	27289	139629	0	17	0	0
SUB 3 BYPASS	0	0	0	0	190485	0	42988	0	0	0	0
SUB 4 BYPASS	0	5	0	0	510334	0	260349	0	0	0	732
SUB 5 BYPASS	0	38238	2370086	0	1587294	3660	2772066	0	0	0	0

Lot Impervious Assumptions


	<i>Max. Imp. Assumption</i>	<i>Avg Lot Dimensions</i>	<i>Avg Lot Area</i>	<i>% Impervious</i>
<i>22' Townhome</i>	1500	22 x 75	1650	91%
<i>39' Single Family</i>	2900	39 x 115	4485	65%
<i>40' Single Family</i>	3100	40 x 125	5000	62%
<i>50' Single Family</i>	3600	50 x 123	6150	59%
<i>60' Single Family</i>	4200	60 x 140	8400	50%

Curve Number Assumptions (Composite)

	<i>HSG A</i>	<i>HSG B</i>	<i>HSG C</i>	<i>HSG D</i>
<i>22' Townhome</i>	93	95	96	96
<i>39' Single Family</i>	77	85	90	92
<i>40' Single Family</i>	76	84	89	91
<i>50' Single Family</i>	74	83	88	91
<i>60' Single Family</i>	69	80	86	89

Lot Breakdown Assumptions

	<i>Roof</i>	<i>Sidewalk</i>	<i>Driveway</i>
<i>22' Townhome</i>	70%	10%	20%
<i>39' Single Family</i>	70%	10%	20%
<i>40' Single Family</i>	70%	10%	20%
<i>50' Single Family</i>	70%	10%	20%
<i>60' Single Family</i>	70%	10%	20%



**FlexTable: Catchment
Table (AWH20000-
CDPackage2.ppc)**

Current Time: 0.00 min

Label	Outflow Node	Area (ft ²)	SCS CN	Time of Concentration (min)	Notes
Sub 2	POA 2	2,377,665	87	31.12	POST
Sub 1 Bypass	POA 1	8,566,708	87	40.80	POST
Sub 1 to SCM A	SCM A	541,712	85	5.00	POST
Sub 1 to SCM D	SCM D	575,524	81	5.00	POST
Sub 1 to SCM C	SCM C	683,134	86	5.00	POST
Sub 1 to SCM E	SCM E	749,339	87	5.00	POST
Sub 4 to SCM F	SCM F	1,004,058	89	5.00	POST
Sub 4 Bypass	POA 4	3,364,834	79	33.28	POST
Sub 4 to SCM G	SCM G	595,094	90	5.00	POST
Sub 4 to SCM H	SCM H	714,538	89	5.00	POST
Sub 5 to SCM J	SCM J	618,061	85	5.00	POST
Sub 4 to SCM I	SCM I	364,606	87	5.00	POST
Sub 1 to SCM B	SCM B	447,048	87	5.00	POST
Sub 3	POA 3	234,442	77	15.64	POST
Sub 5 Bypass	POA 5	17,868,706	80	48.15	POST

Catchments Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (min)	Peak Flow (ft ³ /s)
Sub 2	Post-Dev 1 yr	1	7.297	739.00	70.4
Sub 2	Post-Dev 10 yr	10	16.357	738.00	139.4
Sub 2	Post-Dev 25 yr	25	20.492	738.00	165.4
Sub 2	Post-Dev 100 yr	100	27.422	738.00	204.4
Sub 1 Bypass	Post-Dev 1 yr	1	26.222	745.00	214.1
Sub 1 Bypass	Post-Dev 10 yr	10	58.798	745.00	431.6
Sub 1 Bypass	Post-Dev 25 yr	25	73.674	745.00	515.6
Sub 1 Bypass	Post-Dev 100 yr	100	98.640	745.00	644.7
Sub 1 to SCM A	Post-Dev 1 yr	1	1.523	721.00	32.8
Sub 1 to SCM A	Post-Dev 10 yr	10	3.543	721.00	64.3
Sub 1 to SCM A	Post-Dev 25 yr	25	4.473	721.00	75.3
Sub 1 to SCM A	Post-Dev 100 yr	100	6.034	721.00	91.2
Sub 1 to SCM D	Post-Dev 1 yr	1	1.327	722.00	28.0
Sub 1 to SCM D	Post-Dev 10 yr	10	3.341	721.00	61.0
Sub 1 to SCM D	Post-Dev 25 yr	25	4.291	721.00	73.0
Sub 1 to SCM D	Post-Dev 100 yr	100	5.902	721.00	90.5
Sub 1 to SCM C	Post-Dev 1 yr	1	2.014	721.00	43.5
Sub 1 to SCM C	Post-Dev 10 yr	10	4.598	721.00	83.2
Sub 1 to SCM C	Post-Dev 25 yr	25	5.781	721.00	97.0
Sub 1 to SCM C	Post-Dev 100 yr	100	7.762	721.00	116.8
Sub 1 to SCM E	Post-Dev 1 yr	1	2.316	721.00	50.1
Sub 1 to SCM E	Post-Dev 10 yr	10	5.189	721.00	93.5
Sub 1 to SCM E	Post-Dev 25 yr	25	6.496	721.00	108.5
Sub 1 to SCM E	Post-Dev 100 yr	100	8.681	721.00	130.0
Sub 4 to SCM F	Post-Dev 1 yr	1	3.403	721.00	73.6
Sub 4 to SCM F	Post-Dev 10 yr	10	7.347	721.00	131.2
Sub 4 to SCM F	Post-Dev 25 yr	25	9.123	721.00	150.7
Sub 4 to SCM F	Post-Dev 100 yr	100	12.081	721.00	178.7
Sub 4 Bypass	Post-Dev 1 yr	1	6.923	741.00	61.4
Sub 4 Bypass	Post-Dev 10 yr	10	18.194	741.00	150.8
Sub 4 Bypass	Post-Dev 25 yr	25	23.601	741.00	187.1
Sub 4 Bypass	Post-Dev 100 yr	100	32.855	741.00	243.0
Sub 4 to SCM G	Post-Dev 1 yr	1	2.111	721.00	45.5
Sub 4 to SCM G	Post-Dev 10 yr	10	4.474	721.00	79.4
Sub 4 to SCM G	Post-Dev 25 yr	25	5.533	721.00	90.8
Sub 4 to SCM G	Post-Dev 100 yr	100	7.294	721.00	107.2
Sub 4 to SCM H	Post-Dev 1 yr	1	2.422	721.00	52.3
Sub 4 to SCM H	Post-Dev 10 yr	10	5.228	721.00	93.4
Sub 4 to SCM H	Post-Dev 25 yr	25	6.492	721.00	107.2
Sub 4 to SCM H	Post-Dev 100 yr	100	8.597	721.00	127.2
Sub 5 to SCM J	Post-Dev 1 yr	1	1.737	721.00	37.4
Sub 5 to SCM J	Post-Dev 10 yr	10	4.043	721.00	73.4
Sub 5 to SCM J	Post-Dev 25 yr	25	5.104	721.00	85.9
Sub 5 to SCM J	Post-Dev 100 yr	100	6.885	721.00	104.1
Sub 4 to SCM I	Post-Dev 1 yr	1	1.127	721.00	24.4
Sub 4 to SCM I	Post-Dev 10 yr	10	2.525	721.00	45.5
Sub 4 to SCM I	Post-Dev 25 yr	25	3.161	721.00	52.8
Sub 4 to SCM I	Post-Dev 100 yr	100	4.224	721.00	63.2
Sub 1 to SCM B	Post-Dev 1 yr	1	1.382	721.00	29.9
Sub 1 to SCM B	Post-Dev 10 yr	10	3.095	721.00	55.8
Sub 1 to SCM B	Post-Dev 25 yr	25	3.875	721.00	64.7
Sub 1 to SCM B	Post-Dev 100 yr	100	5.179	721.00	77.5
Sub 3	Post-Dev 1 yr	1	0.435	730.00	5.8
Sub 3	Post-Dev 10 yr	10	1.193	728.00	14.6
Sub 3	Post-Dev 25 yr	25	1.562	728.00	18.0
Sub 3	Post-Dev 100 yr	100	2.195	728.00	23.1


Pond Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (min)	Peak Flow (ft ³ /s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storage (ac-ft)
SCM J (IN)	Post-Dev 1 yr	1	1.737	721.00	37.4	(N/A)	(N/A)
SCM J (OUT)	Post-Dev 1 yr	1	0.615	900.00	1.2	313.11	1.160
SCM J (IN)	Post-Dev 10 yr	10	4.043	721.00	73.4	(N/A)	(N/A)
SCM J (OUT)	Post-Dev 10 yr	10	2.897	731.00	23.0	314.35	1.755
SCM J (IN)	Post-Dev 25 yr	25	5.104	721.00	85.9	(N/A)	(N/A)
SCM J (OUT)	Post-Dev 25 yr	25	3.952	727.00	48.2	314.72	1.943
SCM J (IN)	Post-Dev 100 yr	100	6.885	721.00	104.1	(N/A)	(N/A)
SCM J (OUT)	Post-Dev 100 yr	100	5.732	725.00	74.0	315.10	2.147
SCM I (IN)	Post-Dev 1 yr	1	1.127	721.00	24.4	(N/A)	(N/A)
SCM I (OUT)	Post-Dev 1 yr	1	0.154	1,440.00	0.2	321.88	0.972
SCM I (IN)	Post-Dev 10 yr	10	2.525	721.00	45.5	(N/A)	(N/A)
SCM I (OUT)	Post-Dev 10 yr	10	1.512	730.00	15.5	322.43	1.142
SCM I (IN)	Post-Dev 25 yr	25	3.161	721.00	52.8	(N/A)	(N/A)
SCM I (OUT)	Post-Dev 25 yr	25	2.148	727.00	28.9	322.81	1.262
SCM I (IN)	Post-Dev 100 yr	100	4.224	721.00	63.2	(N/A)	(N/A)
SCM I (OUT)	Post-Dev 100 yr	100	3.211	725.00	46.1	323.22	1.392
SCM G (IN)	Post-Dev 1 yr	1	2.111	721.00	45.5	(N/A)	(N/A)
SCM G (OUT)	Post-Dev 1 yr	1	0.378	1,440.00	0.4	343.67	1.733
SCM G (IN)	Post-Dev 10 yr	10	4.474	721.00	79.4	(N/A)	(N/A)
SCM G (OUT)	Post-Dev 10 yr	10	2.660	733.00	20.3	344.42	2.170
SCM G (IN)	Post-Dev 25 yr	25	5.533	721.00	90.8	(N/A)	(N/A)
SCM G (OUT)	Post-Dev 25 yr	25	3.716	728.00	40.9	344.83	2.418
SCM G (IN)	Post-Dev 100 yr	100	7.294	721.00	107.2	(N/A)	(N/A)
SCM G (OUT)	Post-Dev 100 yr	100	5.476	727.00	62.7	345.33	2.727

STORMWATER CONTROL MEASURE 'B'
DESIGN CALCULATIONS

STAGE-STORAGE FUNCTION - ABOVE NORMAL POOL

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
376.00	0.00	9,314				
377.00	1.00	11,965	10640	10640	10640	1.01
378.00	2.00	13,375	12670	12670	23310	1.97
380.00	4.00	16,627	15001	30002	53312	3.97
382.00	6.00	18,355	17491	34982	88294	6.08




$K_s =$	10488
$b =$	1.1803

STAGE-STORAGE FUNCTION - MAIN POOL

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
368.50	-0.50	2,669				
369.00	0.00	2,909				
Sediment Storage						
373.00	4.00	5,055	3982	15928	15928	4.01
374.00	5.00	5,654	5355	5355	21283	4.98
375.00	6.00	6,278	5966	5966	27249	5.98
376.00	7.00	6,928	6603	6603	33852	7.03


*surface area and volume used for avg. depth calculation



$K_s =$	2453
$b =$	1.3460

STAGE-STORAGE FUNCTION - FOREBAY

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
369.50	-0.50	120				
370.00	0.00	199				
Sediment Storage						
374.00	4.00	1,054	627	2506	2506	4.01
375.00	5.00	1,330	1192	1192	3698	4.98
376.00	6.00	1,632	1481	1481	5179	6.01



$K_s =$	209.3
$b =$	1.7886

TOTAL VOLUME OF FACILITY

Volume of Main Pool below Normal Pool=	33,852	cf
Volume of Forebay below Normal Pool=	5,179	cf
Total Volume Below Normal Pool =	39,031	cf
Total Volume Above Normal Pool=	88,294	cf
Total Volume of Facility =	127,324	cf

FOREBAY PERCENTAGE OF PERMANENT POOL VOLUME

Per NCDEQ Minimum Design Criteria, the forebay volume should equal approximately 15-20% of the main pool volume.

Total Main Pool Volume =	33,852	cf
Provided Forebay Volume =	5,179	cf
Provided Forebay Volume % =	15%	

AVERAGE DEPTH OF MAIN POOL

Main Pool Volume at Normal Pool =	33,852	cf
Main Pool Area at Normal Pool =	6,928	sf
Average Depth =	4.89	ft

WET DETENTION BASIN SUMMARY

Enter the drainage area characteristics ==>

Total drainage area to pond = 10.26 acres
Total impervious area to pond = 6.11 acres

Note The basin must be sized to treat all impervious surface runoff draining into the pond, not just the impervious surface from on-site development.

Drainage area = **10.26** acres @ **59.6%** impervious

Estimate the surface area required at pond normal pool elevation ==>

Wet Detention Basins are based on an minimum average depth of = **4.89** feet

		4.0	4.89	5.0
Lower Boundary =>	50.0	1.51		1.31
Site % impervious =>	59.6	1.76	1.51	1.48
Upper Boundary =>	60.0	1.77		1.49

Therefore, SA/DA required = **1.51**

Surface area required for main pool at normal pool = 6,766 ft²
= 0.16 acres
Surface area provided for total normal pool = 9,314 ft²
Surface area provided for main pool at normal pool = 6,928 ft²

9134

DETERMINATION OF WATER QUALITY VOLUME

$$WQ_v = (P)(R_v)(A)/12$$

where,

WQ_v = water quality volume (in acre-ft)

R_v = 0.05+0.009(I) where I is percent impervious cover

A = area in acres

P = rainfall (in inches)

Input data:

Total area, A =	10.26	acres
Impervious area =	6.11	acres
Percent impervious cover, I =	59.6	%
Rainfall, P =	1.00	inches

Calculated values:

R _v =	0.59	
WQ _v =	0.50	acre-ft
=	21829	cf.

ASSOCIATED DEPTH IN POND

WQ_v = 21829 cf.

Stage / Storage Data:

Ks =	10488	
b =	1.180	
Zo =	376.00	
Volume in 1" rainfall =	21829	cf.

Calculated values:

Depth of WQv in Basin =	1.86	ft
=	22.33	inches
Elevation =	377.86	ft

DRAWDOWN ORIFICE DESIGN

D orifice = 2 inch
 # orifices = 1
 Ks = 10488
 b = 1.1803
 C_d orifice = 0.60
 Normal Pool Elevation = 376.00 feet
 Volume @ Normal Pool = 0 cf
 Orifice Invert = 376.00 feet
 WSEL @ 1" Runoff Volume = 377.86 feet

WSEL (feet)	Vol. Stored (cf)	Orifice Flow (cfs)	Avg. Flow (cfs)	Incr. Vol. (cf)	Incr. Time (sec)
377.86	21829	0.140			
377.70	19637	0.133	0.137	2193	16051
377.54	17481	0.127	0.130	2156	16581
377.38	15365	0.120	0.123	2116	17191
377.22	13292	0.112	0.116	2072	17907
377.06	11269	0.104	0.108	2024	18764
376.90	9299	0.095	0.099	1970	19821
376.74	7391	0.085	0.090	1908	21176
376.58	5557	0.074	0.080	1835	23018
376.42	3811	0.061	0.068	1745	25776
376.26	2183	0.045	0.053	1628	30760

Drawdown Time = 2.40 days

By comparison, if calculated by the average head over the orifice
 (assuming average head is one-third the total depth), the result would be:

Average driving head on orifice = 0.593 feet
 Orifice composite loss coefficient = 0.600
 Cross-sectional area of siphon = 0.022 sf
 Q = 0.0809 cfs

Drawdown Time = Volume / Flowrate / 86400 (sec/day)

Drawdown Time = 3.12 days

RISER ANTI-FLOTATION CALCULATION

Input Data ==>

Safety Factor:

Safety factor to use = 1.15 (recommend 1.15 or higher)

Concrete:

Concrete unit weight = 142.0 PCF

Note: NC Products lists unit wt. of manhole concrete at 142 PCF.

Riser:

Inside height of Riser = 5.00 feet
Inside length of riser = 4.00 feet
Inside width of riser = 4.00 feet
Wall thickness of riser = 6.00 inches
Base thickness of riser = 6.00 inches
Base length of riser = 5.00 feet
Base width of riser = 5.00 feet

Openings:

Total Orifice Area = 4.587 SF
OD of barrel exiting manhole = 30.00 inches
Size of drain pipe (if present) = 6.0 inches

Trash Rack:

Bottom Length = 7.00 feet
Bottom Width = 7.00 feet
Top Length = 1.00 feet
Top Width = 1.00 feet
Height = 2.00 feet
Trash Rack water displacement = 38.00 CF

Concrete Present in Riser Structure ==>

Total amount of concrete:

Base of Riser = 12.50 CF
Riser Walls = 45.00 CF

Adjust for openings:

Opening for Orifices = 2.29 CF
Opening for barrel = 2.45 CF
Opening for drain pipe = 0.10 CF

Total Concrete present, adjusted for openings = **52.654 CF**
Weight of concrete present = **7,477 lbs**

Amount of water displaced by Riser Structure ==>

Displacement by concrete =	52.65 CF
Displacement by open air in riser =	80.00 CF
Displacement by trash rack =	38.00 CF
Total water displaced by riser/barrel structure =	170.65 CF
Weight of water displaced =	10,649 lbs

Calculate size of base for riser assembly ==>

Length =	8.00 feet
Width =	8.00 feet
Thickness =	12 inches
Concrete Present =	64.00 CF

Check validity of base as designed ==>

Total Water Displaced =	222.15 CF
Total Concrete Present =	116.65 CF
Total Water Displaced =	13,862 lbs
Total Concrete Present =	16,565 lbs
Actual safety factor =	1.19 OK

Results of design ==>

Base length =	8.00 feet
Base width =	8.00 feet
Base Thickness =	12.00 inches
CY of concrete total in base =	2.37 CY
Concrete unit weight in added base >=	142.0 PCF

II. CALCULATION FOR RISER ANTI-FLOTATION STEEL

Input Data ==>

Anti-Floatation Block Length = 8.0 feet
Anti-Floatation Block Width = 8.0 feet
Anti-Floatation Block Thickness = 12 inches

A_{steel} to A_{concrete} Ratio = 0.0020 (recommend 0.0018 or hi

Cross-Section Calculations==>

Cross-Section Area* = 8.00 SF
Minimum Steel Area Required = 0.016 SF
2.30 SI

**Note: Assumes a "square" x-sec (L and W same)*

Rebar Calculations ==>

Bar Size	4	5	6	7	8
Diameter (inches)	0.500	0.625	0.750	0.875	1.000
X-Sec Area (SI)	0.196	0.307	0.442	0.601	0.785
Minimum Number of Bars	12	8	6	4	3


DESIGN OF RIPRAP OUTLET PROTECTION WORKSHEET

Project The Point
 Project No. AWH-20000
 Outlet ID SCM B

Date 8/2/2021
 Designer TKD

Flow, $Q_{10\text{-yr}}$ 22.5 cfs
 Slope, S 2.00 %
 Pipe Diameter, D_o 24 inches
 Pipe Diameter, D_o 2.0 feet
 Number of pipes 1
 Pipe separation 0 feet
 Manning's n 0.013

Figure 8.06.b.1



Zone from graph above = 3

Outlet pipe diameter 24 in. Length = 16.0 ft.
 Outlet flowrate 22.5 cfs Width = 6.0 ft.
 Outlet velocity 11.1 ft/sec Stone diameter = 13 in.
 Material = Class I Thickness = 22 in.


Zone	Material	Diameter	Thickness	Length	Width
1	Class A	3	9	4 x D(o)	3 x D(o)
2	Class B	6	22	6 x D(o)	3 x D(o)
3	Class I	13	22	8 x D(o)	3 x D(o)
4	Class I	13	22	8 x D(o)	3 x D(o)
5	Class II	23	27	10 x D(o)	3 x D(o)
6	Class II	23	27	10 x D(o)	3 x D(o)
7	Special study required				

- Calculations based on NY DOT method - Pages 8.06.05 through 8.06.06 in NC Erosion Control Manual
- Outlet velocity based on full-flow velocity

*STORMWATER CONTROL MEASURE 'G'
DESIGN CALCULATIONS*

STAGE-STORAGE FUNCTION - ABOVE NORMAL POOL

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
340.00	0.00	15,673				
341.00	1.00	19,251	17462	17462	17462	1.01
342.00	2.00	21,125	20188	20188	37650	1.97
344.00	4.00	25,043	23084	46168	83818	3.95
346.00	6.00	29,187	27115	54230	138048	6.09




$K_s =$	17230
$b =$	1.1516

STAGE-STORAGE FUNCTION - MAIN POOL

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
335.00	-1.00	8,242				
336.00	0.00	9,028				
337.00	1.00	9,838	9433	9433	9433	1.01
338.00	2.00	10,674	10256	10256	19689	1.98
339.00	3.00	11,535	11105	11105	30794	2.98
340.00	4.00	12,421	11978	11978	42772	4.04


*surface area and volume used for avg. depth calculation



$K_s =$	9368
$b =$	1.0881

STAGE-STORAGE FUNCTION - FOREBAY

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
336.00	-1.00	1,259				
337.00	0.00	1,574				
338.00	1.00	1,915	1745	1745	1745	1.00
339.00	2.00	2,280	2098	2098	3842	1.98
340.00	3.00	2,671	2476	2476	6318	3.02



$K_s =$	1735.1
$b =$	1.1679

TOTAL VOLUME OF FACILITY

Volume of Main Pool below Normal Pool=	42,772	cf
Volume of Forebay below Normal Pool=	6,318	cf
Total Volume Below Normal Pool =	49,089	cf
Total Volume Above Normal Pool=	138,048	cf
Total Volume of Facility =	187,137	cf

FOREBAY PERCENTAGE OF PERMANENT POOL VOLUME

Per NCDEQ Minimum Design Criteria, the forebay volume should equal approximately 15-20% of the main pool volume.

Total Main Pool Volume =	42,772	cf
Provided Forebay Volume =	6,318	cf
Provided Forebay Volume % =	15%	

AVERAGE DEPTH OF MAIN POOL

Main Pool Volume at Normal Pool =	42,772	cf
Main Pool Area at Normal Pool =	12,421	sf
Average Depth =	3.44	ft

WET DETENTION BASIN SUMMARY

Enter the drainage area characteristics ==>

Total drainage area to pond = 13.66 acres
Total impervious area to pond = 8.16 acres

Note The basin must be sized to treat all impervious surface runoff draining into the pond, not just the impervious surface from on-site development.

Drainage area = **13.66** acres @ **59.8%** impervious

Estimate the surface area required at pond normal pool elevation ==>

Wet Detention Basins are based on an minimum average depth of = **3.44** feet

		3.0	3.44	4.0
Lower Boundary =>	50.0	1.79		1.51
Site % impervious =>	59.8	2.08	1.94	1.76
Upper Boundary =>	60.0	2.09		1.77

Therefore, SA/DA required = **1.94**

Surface area required for main pool at normal pool = 11,552 ft²
= 0.27 acres
Surface area provided for total normal pool = 15,673 ft²
Surface area provided for main pool at normal pool = 12,421 ft²

DETERMINATION OF WATER QUALITY VOLUME

$$WQ_v = (P)(R_v)(A)/12$$

where,

WQ_v = water quality volume (in acre-ft)

R_v = 0.05+0.009(I) where I is percent impervious cover

A = area in acres

P = rainfall (in inches)

Input data:

Total area, A =	13.66	acres
Impervious area =	8.16	acres
Percent impervious cover, I =	59.8	%
Rainfall, P =	1.00	inches

Calculated values:

R _v =	0.59	
WQ _v =	0.67	acre-ft
=	29149	cf.

ASSOCIATED DEPTH IN POND

WQ_v = 29149 cf.

Stage / Storage Data:

Ks =	17230	
b =	1.152	
Zo =	340.00	
Volume in 1" rainfall =	29149	cf.

Calculated values:

Depth of WQv in Basin =	1.58	ft
=	18.94	inches
Elevation =	341.58	ft

DRAWDOWN ORIFICE DESIGN

D orifice = 2.5 inch
 # orifices = 1
 Ks = 17230
 b = 1.1516
 C_d orifice = 0.60
 Normal Pool Elevation = 340.00 feet
 Volume @ Normal Pool = 0 cf
 Orifice Invert = 340.00 feet
 WSEL @ 1" Runoff Volume = 341.58 feet

WSEL (feet)	Vol. Stored (cf)	Orifice Flow (cfs)	Avg. Flow (cfs)	Incr. Vol. (cf)	Incr. Time (sec)
341.58	29149	0.199			
341.44	26267	0.190	0.194	2883	14839
341.31	23425	0.180	0.185	2842	15394
341.17	20628	0.169	0.174	2797	16040
341.03	17880	0.158	0.164	2748	16804
340.90	15187	0.146	0.152	2693	17732
340.76	12556	0.133	0.139	2631	18895
340.62	9995	0.118	0.125	2560	20421
340.49	7519	0.101	0.110	2476	22569
340.35	5147	0.081	0.091	2372	25970
340.21	2915	0.054	0.068	2232	32940

Drawdown Time = 2.33 days

By comparison, if calculated by the average head over the orifice
 (assuming average head is one-third the total depth), the result would be:

Average driving head on orifice = 0.492 feet
 Orifice composite loss coefficient = 0.600
 Cross-sectional area of siphon = 0.034 sf

 Q = 0.1151 cfs

Drawdown Time = Volume / Flowrate / 86400 (sec/day)

Drawdown Time = 2.93 days

RISER ANTI-FLOTATION CALCULATION

Input Data ==>

Safety Factor:

Safety factor to use = 1.15 (recommend 1.15 or higher)

Concrete:

Concrete unit weight = 142.0 PCF

Note: NC Products lists unit wt. of manhole concrete at 142 PCF.

Riser:

Inside height of Riser = 5.50 feet
Inside length of riser = 5.00 feet
Inside width of riser = 5.00 feet
Wall thickness of riser = 6.00 inches
Base thickness of riser = 6.00 inches
Base length of riser = 6.00 feet
Base width of riser = 6.00 feet

Openings:

Total Orifice Area = 15.087 SF
OD of barrel exiting manhole = 44.00 inches
Size of drain pipe (if present) = 6.0 inches

Trash Rack:

Bottom Length = 8.40 feet
Bottom Width = 8.40 feet
Top Length = 2.10 feet
Top Width = 2.10 feet
Height = 2.00 feet
Trash Rack water displacement = 61.74 CF

Concrete Present in Riser Structure ==>

Total amount of concrete:

Base of Riser = 18.00 CF
Riser Walls = 60.50 CF

Adjust for openings:

Opening for Orifices = 7.54 CF
Opening for barrel = 5.28 CF
Opening for drain pipe = 0.10 CF

Total Concrete present, adjusted for openings = **65.579 CF**
Weight of concrete present = **9,312 lbs**

Amount of water displaced by Riser Structure ==>

Displacement by concrete =	65.58 CF
Displacement by open air in riser =	137.50 CF
Displacement by trash rack =	61.74 CF
Total water displaced by riser/barrel structure =	264.82 CF
Weight of water displaced =	16,525 lbs

Calculate size of base for riser assembly ==>

Length =	9.00 feet
Width =	9.00 feet
Thickness =	18 inches
Concrete Present =	121.50 CF

Check validity of base as designed ==>

Total Water Displaced =	368.32 CF
Total Concrete Present =	187.08 CF
Total Water Displaced =	22,983 lbs
Total Concrete Present =	26,565 lbs
Actual safety factor =	1.16 OK

Results of design ==>

Base length =	9.00 feet
Base width =	9.00 feet
Base Thickness =	18.00 inches
CY of concrete total in base =	4.50 CY
Concrete unit weight in added base >=	142.0 PCF

II. CALCULATION FOR RISER ANTI-FLOTATION STEEL

Input Data ==>

Anti-Floatation Block Length = 9.0 feet
Anti-Floatation Block Width = 9.0 feet
Anti-Floatation Block Thickness = 18 inches

A_{steel} to A_{concrete} Ratio = 0.0020 (recommend 0.0018 or hi

Cross-Section Calculations==>

Cross-Section Area* = 13.50 SF
Minimum Steel Area Required = 0.027 SF
3.89 SI

**Note: Assumes a "square" x-sec (L and W same)*

Rebar Calculations ==>

Bar Size	4	5	6	7	8
Diameter (inches)	0.500	0.625	0.750	0.875	1.000
X-Sec Area (SI)	0.196	0.307	0.442	0.601	0.785
Minimum Number of Bars	20	13	9	7	5


DESIGN OF RIPRAP OUTLET PROTECTION WORKSHEET

Project The Point
 Project No. AWH-20000
 Outlet ID SCM G

Date 11/23/2020
 Designer TKD

Flow, $Q_{10\text{-yr}}$ 20.3 cfs
 Slope, S 1.03 %
 Pipe Diameter, D_o 36 inches
 Pipe Diameter, D_o 3.0 feet
 Number of pipes 1
 Pipe separation 0 feet
 Manning's n 0.013

Figure 8.06.b.1



Zone from graph above = 3

Outlet pipe diameter 36 in. Length = 24.0 ft.
 Outlet flowrate 20.3 cfs Width = 9.0 ft.
 Outlet velocity 8.4 ft/sec Stone diameter = 13 in.
 Material = Class I Thickness = 22 in.


Zone	Material	Diameter	Thickness	Length	Width
1	Class A	3	9	4 x D(o)	3 x D(o)
2	Class B	6	22	6 x D(o)	3 x D(o)
3	Class I	13	22	8 x D(o)	3 x D(o)
4	Class I	13	22	8 x D(o)	3 x D(o)
5	Class II	23	27	10 x D(o)	3 x D(o)
6	Class II	23	27	10 x D(o)	3 x D(o)
7	Special study required				

- Calculations based on NY DOT method - Pages 8.06.05 through 8.06.06 in NC Erosion Control Manual
- Outlet velocity based on full-flow velocity

STORMWATER CONTROL MEASURE 'H'
DESIGN CALCULATIONS

STAGE-STORAGE FUNCTION - ABOVE NORMAL POOL

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
330.00	0.00	18,403				
331.00	1.00	22,307	20355	20355	20355	1.01
332.00	2.00	24,345	23326	23326	43681	1.97
334.00	4.00	28,589	26467	52934	96615	3.95
336.00	6.00	33,059	30824	61648	158263	6.09




$K_s =$	20099
$b =$	1.1424

STAGE-STORAGE FUNCTION - MAIN POOL

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
325.00	-1.00	8,549				
326.00	0.00	9,614				
327.00	1.00	10,703	10159	10159	10159	1.01
328.00	2.00	11,818	11261	11261	21419	1.98
329.00	3.00	12,958	12388	12388	33807	2.98
330.00	4.00	14,123	13541	13541	47348	4.04


*surface area and volume used for avg. depth calculation



$K_s =$	10076
$b =$	1.1076

STAGE-STORAGE FUNCTION - FOREBAY

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
326.00	-1.00	2,040				
327.00	0.00	2,389				
328.00	1.00	2,763	2576	2576	2576	1.00
329.00	2.00	3,162	2963	2963	5539	1.98
330.00	3.00	3,586	3374	3374	8913	3.02



$K_s =$	2565.1
$b =$	1.1271

TOTAL VOLUME OF FACILITY

Volume of Main Pool below Normal Pool=	47,348	cf
Volume of Forebay below Normal Pool=	8,913	cf
Total Volume Below Normal Pool =	56,260	cf
Total Volume Above Normal Pool=	158,263	cf
Total Volume of Facility =	214,523	cf

FOREBAY PERCENTAGE OF PERMANENT POOL VOLUME

Per NCDEQ Minimum Design Criteria, the forebay volume should equal approximately 15-20% of the main pool volume.

Total Main Pool Volume =	47,348	cf
Provided Forebay Volume =	8,913	cf
Provided Forebay Volume % =	19%	

AVERAGE DEPTH OF MAIN POOL

Main Pool Volume at Normal Pool =	47,348	cf
Main Pool Area at Normal Pool =	14,123	sf
Average Depth =	3.35	ft

WET DETENTION BASIN SUMMARY

Enter the drainage area characteristics ==>

Total drainage area to pond = 16.40 acres
Total impervious area to pond = 9.15 acres

Note The basin must be sized to treat all impervious surface runoff draining into the pond, not just the impervious surface from on-site development.

Drainage area = **16.40** acres @ **55.8%** impervious

Estimate the surface area required at pond normal pool elevation ==>

Wet Detention Basins are based on an minimum average depth of = **3.35** feet

		3.0	3.35	4.0
Lower Boundary =>	50.0	1.79		1.51
Site % impervious =>	55.8	1.96	1.86	1.66
Upper Boundary =>	60.0	2.09		1.77

Therefore, SA/DA required = **1.86**

Surface area required for main pool at normal pool = 13,269 ft²
= 0.30 acres
Surface area provided for total normal pool = 18,403 ft²
Surface area provided for main pool at normal pool = 14,123 ft²

DETERMINATION OF WATER QUALITY VOLUME

$$WQ_v = (P)(R_v)(A)/12$$

where,

WQ_v = water quality volume (in acre-ft)

R_v = 0.05+0.009(I) where I is percent impervious cover

A = area in acres

P = rainfall (in inches)

Input data:

Total area, A =	16.40	acres
Impervious area =	9.15	acres
Percent impervious cover, I =	55.8	%
Rainfall, P =	1.00	inches

Calculated values:

R _v =	0.55	
WQ _v =	0.75	acre-ft
=	32877	cf.

ASSOCIATED DEPTH IN POND

WQ_v = 32877 cf.

Stage / Storage Data:

Ks =	20099	
b =	1.142	
Zo =	330.00	
Volume in 1" rainfall =	32877	cf.

Calculated values:

Depth of WQv in Basin =	1.54	ft
=	18.46	inches
Elevation =	331.54	ft

DRAWDOWN ORIFICE DESIGN

D orifice = 2.75 inch
 # orifices = 1
 Ks = 20099
 b = 1.1424
 C_d orifice = 0.60
 Normal Pool Elevation = 330.00 feet
 Volume @ Normal Pool = 0 cf
 Orifice Invert = 330.00 feet
 WSEL @ 1" Runoff Volume = 331.54 feet

WSEL (feet)	Vol. Stored (cf)	Orifice Flow (cfs)	Avg. Flow (cfs)	Incr. Vol. (cf)	Incr. Time (sec)
331.54	32877	0.237			
331.41	29643	0.225	0.231	3235	14008
331.27	26451	0.213	0.219	3191	14554
331.14	23307	0.201	0.207	3144	15191
331.01	20215	0.187	0.194	3092	15948
330.87	17181	0.173	0.180	3034	16871
330.74	14213	0.157	0.165	2968	18036
330.61	11321	0.139	0.148	2892	19578
330.47	8518	0.118	0.129	2802	21778
330.34	5828	0.094	0.106	2690	25346
330.21	3288	0.057	0.075	2540	33692

Drawdown Time = 2.26 days

By comparison, if calculated by the average head over the orifice
 (assuming average head is one-third the total depth), the result would be:

Average driving head on orifice = 0.475 feet
 Orifice composite loss coefficient = 0.600
 Cross-sectional area of siphon = 0.041 sf
 Q = 0.1368 cfs

Drawdown Time = Volume / Flowrate / 86400 (sec/day)

Drawdown Time = 2.78 days

RISER ANTI-FLOTATION CALCULATION

Input Data ==>

Safety Factor:

Safety factor to use = 1.15 (recommend 1.15 or higher)

Concrete:

Concrete unit weight = 142.0 PCF

Note: NC Products lists unit wt. of manhole concrete at 142 PCF.

Riser:

Inside height of Riser = 5.50 feet
Inside length of riser = 6.00 feet
Inside width of riser = 6.00 feet
Wall thickness of riser = 6.00 inches
Base thickness of riser = 6.00 inches
Base length of riser = 7.00 feet
Base width of riser = 7.00 feet

Openings:

Total Orifice Area = 7.665 SF
OD of barrel exiting manhole = 51.00 inches
Size of drain pipe (if present) = 6.0 inches

Trash Rack:

Bottom Length = 7.00 feet
Bottom Width = 7.00 feet
Top Length = 1.00 feet
Top Width = 1.00 feet
Height = 2.00 feet
Trash Rack water displacement = 38.00 CF

Concrete Present in Riser Structure ==>

Total amount of concrete:

Base of Riser = 24.50 CF
Riser Walls = 71.50 CF

Adjust for openings:

Opening for Orifices = 3.83 CF
Opening for barrel = 7.09 CF
Opening for drain pipe = 0.10 CF

Total Concrete present, adjusted for openings = **84.976 CF**
Weight of concrete present = **12,067 lbs**

Amount of water displaced by Riser Structure ==>

Displacement by concrete =	84.98 CF
Displacement by open air in riser =	198.00 CF
Displacement by trash rack =	38.00 CF
Total water displaced by riser/barrel structure =	320.98 CF
Weight of water displaced =	20,029 lbs

Calculate size of base for riser assembly ==>

Length =	10.00 feet
Width =	10.00 feet
Thickness =	24 inches
Concrete Present =	200.00 CF

Check validity of base as designed ==>

Total Water Displaced =	496.48 CF
Total Concrete Present =	284.98 CF
Total Water Displaced =	30,980 lbs
Total Concrete Present =	40,467 lbs
Actual safety factor =	1.31 OK

Results of design ==>

Base length =	10.00 feet
Base width =	10.00 feet
Base Thickness =	24.00 inches
CY of concrete total in base =	7.41 CY
Concrete unit weight in added base >=	142.0 PCF

II. CALCULATION FOR RISER ANTI-FLOTATION STEEL

Input Data ==>

Anti-Floatation Block Length = 10.0 feet
Anti-Floatation Block Width = 10.0 feet
Anti-Floatation Block Thickness = 24 inches

A_{steel} to A_{concrete} Ratio = 0.0020 (recommend 0.0018 or hi

Cross-Section Calculations==>

Cross-Section Area* = 20.00 SF
Minimum Steel Area Required = 0.040 SF
5.76 SI

**Note: Assumes a "square" x-sec (L and W same)*

Rebar Calculations ==>

Bar Size	4	5	6	7	8
Diameter (inches)	0.500	0.625	0.750	0.875	1.000
X-Sec Area (SI)	0.196	0.307	0.442	0.601	0.785
Minimum Number of Bars	30	19	14	10	8


DESIGN OF RIPRAP OUTLET PROTECTION WORKSHEET

Project The Point
 Project No. AWH-20000
 Outlet ID SCM H

Date 11/23/2020
 Designer TKD

Flow, $Q_{10\text{-yr}}$ 23.5 cfs
 Slope, S 1.25 %
 Pipe Diameter, D_o 42 inches
 Pipe Diameter, D_o 3.5 feet
 Number of pipes 1
 Pipe separation 0 feet
 Manning's n 0.013

Figure 8.06.b.1



Zone from graph above = 3

Outlet pipe diameter 42 in. Length = 28.0 ft.
 Outlet flowrate 23.5 cfs Width = 10.5 ft.
 Outlet velocity 9.3 ft/sec Stone diameter = 13 in.
 Material = Class I Thickness = 22 in.


Zone	Material	Diameter	Thickness	Length	Width
1	Class A	3	9	4 x D(o)	3 x D(o)
2	Class B	6	22	6 x D(o)	3 x D(o)
3	Class I	13	22	8 x D(o)	3 x D(o)
4	Class I	13	22	8 x D(o)	3 x D(o)
5	Class II	23	27	10 x D(o)	3 x D(o)
6	Class II	23	27	10 x D(o)	3 x D(o)
7	Special study required				

- Calculations based on NY DOT method - Pages 8.06.05 through 8.06.06 in NC Erosion Control Manual
- Outlet velocity based on full-flow velocity

STORMWATER CONTROL MEASURE 'I'
DESIGN CALCULATIONS

STAGE-STORAGE FUNCTION - ABOVE NORMAL POOL

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
318.00	0.00	7,619				
319.00	1.00	10,306	8963	8963	8963	1.01
320.00	2.00	11,734	11020	11020	19983	1.98
322.00	4.00	13,880	12807	25614	45597	3.97
324.00	6.00	15,964	14922	29844	75441	6.06




$K_s =$	8878
$b =$	1.1874

STAGE-STORAGE FUNCTION - MAIN POOL

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
308.50	-0.50	732				
309.00	0.00	866				
315.00	6.00	3,503	2185	13107	13107	6.01
316.00	7.00	4,029	3766	3766	16873	6.98
317.00	8.00	4,580	4305	4305	21178	7.98
318.00	9.00	5,157	4869	4869	26046	9.02


*surface area and volume used for avg. depth calculation



$K_s =$	629
$b =$	1.6928

STAGE-STORAGE FUNCTION - FOREBAY

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
340.50	-0.50	22				
341.00	0.00	42				
Sediment Storage						
342.00	1.00	101	72	72	72	1.01
343.50	2.50	290	196	293	365	2.41
344.00	3.00	577	434	217	582	3.09




$K_s =$	70.7
$b =$	1.8659

STORMWATER CONTROL MEASURE 'I'
SSFxn Forebay (2)

STAGE-STORAGE FUNCTION - FOREBAY

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
311.50	-0.50	69				
312.00	0.00	109				
Sediment Storage						
316.00	4.00	647	378	1512	1512	4.01
317.00	5.00	844	746	746	2258	4.98
318.00	6.00	1,066	955	955	3213	6.02



$K_s =$	114.8
$b =$	1.8563

TOTAL VOLUME OF FACILITY

Volume of Main Pool below Normal Pool=	26,046	cf
Volume of Forebay below Normal Pool=	3,794	cf
Total Volume Below Normal Pool =	29,840	cf
Total Volume Above Normal Pool=	75,441	cf
Total Volume of Facility =	105,281	cf

FOREBAY PERCENTAGE OF PERMANENT POOL VOLUME

Per NCDEQ Minimum Design Criteria, the forebay volume should equal approximately 15-20% of the main pool volume.

Total Main Pool Volume =	26,046	cf
Provided Forebay Volume =	3,794	cf
Provided Forebay Volume % =	15%	

AVERAGE DEPTH OF MAIN POOL

Main Pool Volume at Normal Pool =	26,046	cf
Main Pool Area at Normal Pool =	5,157	sf
Average Depth =	5.05	ft

WET DETENTION BASIN SUMMARY

Enter the drainage area characteristics ==>

Total drainage area to pond = 8.37 acres
Total impervious area to pond = 4.54 acres

Note The basin must be sized to treat all impervious surface runoff draining into the pond, not just the impervious surface from on-site development.

Drainage area = **8.37** acres @ **54.3%** impervious

Estimate the surface area required at pond normal pool elevation ==>

Wet Detention Basins are based on an minimum average depth of = **5.05** feet (*Hard Coded*)

		5.0	5.05	6.0
Lower Boundary =>	50.0	1.31		1.13
Site % impervious =>	54.3	1.39	1.38	1.21
Upper Boundary =>	60.0	1.49		1.31

Therefore, SA/DA required = **1.38**

Surface area required for main pool at normal pool = 5,024 ft²
= 0.12 acres
Surface area provided for total normal pool = 7,619 ft²
Surface area estimate for main pool at normal pool = 5,157 ft²

6782.306

DETERMINATION OF WATER QUALITY VOLUME

$$WQ_v = (P)(R_v)(A)/12$$

where,

WQ_v = water quality volume (in acre-ft)

R_v = 0.05+0.009(I) where I is percent impervious cover

A = area in acres

P = rainfall (in inches)

Input data:

Total area, A =	8.37	acres
Impervious area =	4.54	acres
Percent impervious cover, I =	54.3	%
Rainfall, P =	1.00	inches

Calculated values:

R _v =	0.54	
WQ _v =	0.38	acre-ft
=	16362	cf.

ASSOCIATED DEPTH IN POND

WQ_v = 16362 cf.

Stage / Storage Data:

Ks =	8878	
b =	1.187	
Zo =	318.00	
Volume in 1" rainfall =	16362	cf.

Calculated values:

Depth of WQv in Basin =	1.67	ft
=	20.08	inches
Elevation =	319.67	ft

DRAWDOWN ORIFICE DESIGN

D orifice = 1.75 inch
 # orifices = 1
 Ks = 8878
 b = 1.1874
 C_d orifice = 0.60
 Normal Pool Elevation = 318.00 feet
 Volume @ Normal Pool = 0 cf
 Orifice Invert = 318.00 feet
 WSEL @ 1" Runoff Volume = 319.67 feet

WSEL (feet)	Vol. Stored (cf)	Orifice Flow (cfs)	Avg. Flow (cfs)	Incr. Vol. (cf)	Incr. Time (sec)
319.67	16362	0.102			
319.53	14712	0.097	0.099	1650	16620
319.39	13091	0.092	0.094	1621	17155
319.24	11501	0.087	0.089	1590	17771
319.10	9945	0.081	0.084	1556	18492
318.96	8427	0.076	0.078	1518	19354
318.81	6951	0.069	0.072	1476	20414
318.67	5523	0.062	0.066	1428	21769
318.53	4152	0.054	0.058	1372	23607
318.38	2849	0.045	0.049	1303	26341
318.24	1636	0.033	0.039	1213	31228

Drawdown Time = 2.46 days

By comparison, if calculated by the average head over the orifice
 (assuming average head is one-third the total depth), the result would be:

Average driving head on orifice = 0.534 feet
 Orifice composite loss coefficient = 0.600
 Cross-sectional area of siphon = 0.017 sf
 Q = 0.0587 cfs

Drawdown Time = Volume / Flowrate / 86400 (sec/day)

Drawdown Time = 3.22 days

RISER ANTI-FLOTATION CALCULATION

Input Data ==>

Safety Factor:

Safety factor to use = 1.15 (recommend 1.15 or higher)

Concrete:

Concrete unit weight = 142.0 PCF

Note: NC Products lists unit wt. of manhole concrete at 142 PCF.

Riser:

Inside height of Riser = 6.00 feet
Inside length of riser = 5.00 feet
Inside width of riser = 5.00 feet
Wall thickness of riser = 6.00 inches
Base thickness of riser = 6.00 inches
Base length of riser = 6.00 feet
Base width of riser = 6.00 feet

Openings:

Total Orifice Area = 9.017 SF
OD of barrel exiting manhole = 44.00 inches
Size of drain pipe (if present) = 6.0 inches

Trash Rack:

Bottom Length = 8.40 feet
Bottom Width = 8.40 feet
Top Length = 2.10 feet
Top Width = 2.10 feet
Height = 2.00 feet
Trash Rack water displacement = 61.74 CF

Concrete Present in Riser Structure ==>

Total amount of concrete:

Base of Riser = 18.00 CF
Riser Walls = 66.00 CF

Adjust for openings:

Opening for Orifices = 4.51 CF
Opening for barrel = 5.28 CF
Opening for drain pipe = 0.10 CF

Total Concrete present, adjusted for openings = **74.114 CF**
Weight of concrete present = **10,524 lbs**

Amount of water displaced by Riser Structure ==>

Displacement by concrete =	74.11 CF
Displacement by open air in riser =	150.00 CF
Displacement by trash rack =	61.74 CF
Total water displaced by riser/barrel structure =	285.85 CF
Weight of water displaced =	17,837 lbs

Calculate size of base for riser assembly ==>

Length =	9.00 feet
Width =	9.00 feet
Thickness =	24 inches
Concrete Present =	162.00 CF

Check validity of base as designed ==>

Total Water Displaced =	429.85 CF
Total Concrete Present =	236.11 CF
Total Water Displaced =	26,823 lbs
Total Concrete Present =	33,528 lbs
Actual safety factor =	1.25 OK

Results of design ==>

Base length =	9.00 feet
Base width =	9.00 feet
Base Thickness =	24.00 inches
CY of concrete total in base =	6.00 CY
Concrete unit weight in added base >=	142.0 PCF

II. CALCULATION FOR RISER ANTI-FLOTATION STEEL

Input Data ==>

Anti-Floatation Block Length = 9.0 feet
Anti-Floatation Block Width = 9.0 feet
Anti-Floatation Block Thickness = 24 inches

A_{steel} to A_{concrete} Ratio = 0.0020 (recommend 0.0018 or hi

Cross-Section Calculations==>

Cross-Section Area* = 18.00 SF
Minimum Steel Area Required = 0.036 SF
5.18 SI

**Note: Assumes a "square" x-sec (L and W same)*

Rebar Calculations ==>

Bar Size	4	5	6	7	8
Diameter (inches)	0.500	0.625	0.750	0.875	1.000
X-Sec Area (SI)	0.196	0.307	0.442	0.601	0.785
Minimum Number of Bars	27	17	12	9	7


DESIGN OF RIPRAP OUTLET PROTECTION WORKSHEET

Project The Point
 Project No. AWH-20000
 Outlet ID SCM F

Date 11/23/2020
 Designer TKD

Flow, $Q_{10\text{-yr}}$ 15.2 cfs
 Slope, S 2.06 %
 Pipe Diameter, D_o 36 inches
 Pipe Diameter, D_o 3.0 feet
 Number of pipes 1
 Pipe separation 0 feet
 Manning's n 0.013

Figure 8.06.b.1



Zone from graph above = 3

Outlet pipe diameter 36 in. Length = 24.0 ft.
 Outlet flowrate 15.2 cfs Width = 9.0 ft.
 Outlet velocity 9.9 ft/sec Stone diameter = 13 in.
 Material = Class I Thickness = 22 in.


Zone	Material	Diameter	Thickness	Length	Width
1	Class A	3	9	4 x D(o)	3 x D(o)
2	Class B	6	22	6 x D(o)	3 x D(o)
3	Class I	13	22	8 x D(o)	3 x D(o)
4	Class I	13	22	8 x D(o)	3 x D(o)
5	Class II	23	27	10 x D(o)	3 x D(o)
6	Class II	23	27	10 x D(o)	3 x D(o)
7	Special study required				

- Calculations based on NY DOT method - Pages 8.06.05 through 8.06.06 in NC Erosion Control Manual
- Outlet velocity based on full-flow velocity

STORMWATER CONTROL MEASURE 'J'
DESIGN CALCULATIONS

STAGE-STORAGE FUNCTION - ABOVE NORMAL POOL

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
310.00	0.00	11,895				
311.00	1.00	15,511	13703	13703	13703	1.01
312.00	2.00	17,403	16457	16457	30160	1.97
314.00	4.00	21,358	19381	38761	68921	3.94
316.00	6.00	25,539	23449	46897	115818	6.10




$K_s =$	13490
$b =$	1.1886

STAGE-STORAGE FUNCTION - MAIN POOL

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
303.50	-0.50	3,710				
304.00	0.00	4,077				
307.00	3.00	6,414	5246	15737	15737	3.01
308.00	4.00	7,243	6829	6829	22565	3.98
309.00	5.00	8,097	7670	7670	30235	4.98
310.00	6.00	8,977	8537	8537	38772	6.03


*surface area and volume used for avg. depth calculation



$K_s =$	3754
$b =$	1.2994

STAGE-STORAGE FUNCTION - FOREBAY


Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
303.50	-0.50	62				
304.00	0.00	105				
Sediment Storage						
308.00	4.00	679	392	1568	1568	4.01
309.00	5.00	886	783	783	2351	4.98
310.00	6.00	1,117	1002	1002	3352	6.02



$K_s =$	116.6
$b =$	1.8716

STAGE-STORAGE FUNCTION - FOREBAY

Contour (feet)	Stage (feet)	Contour Area (SF)	Average Contour Area (SF)	Incremental Contour Volume (CF)	Accumulated Contour Volume (CF)	Estimated Stage w/ S-S Fxn (feet)
304.00	0.00	22				
304.00	0.00	50				
Sediment Storage						
308.00	4.00	481	266	1062	1062	4.01
309.00	5.00	652	567	567	1629	4.97
310.00	6.00	848	750	750	2379	6.02



$K_s =$	67.4
$b =$	1.9859

TOTAL VOLUME OF FACILITY

Volume of Main Pool below Normal Pool=	38,772	cf
Volume of Forebay below Normal Pool=	5,731	cf
Total Volume Below Normal Pool =	44,503	cf
Total Volume Above Normal Pool=	115,818	cf
Total Volume of Facility =	160,321	cf

FOREBAY PERCENTAGE OF PERMANENT POOL VOLUME

Per NCDEQ Minimum Design Criteria, the forebay volume should equal approximately 15-20% of the main pool volume.

Total Main Pool Volume =	38,772	cf
Provided Forebay Volume =	5,731	cf
Provided Forebay Volume % =	15%	

AVERAGE DEPTH OF MAIN POOL

Main Pool Volume at Normal Pool =	38,772	cf
Main Pool Area at Normal Pool =	8,977	sf
Average Depth =	4.32	ft

WET DETENTION BASIN SUMMARY

Enter the drainage area characteristics ==>

Total drainage area to pond = 14.19 acres
Total impervious area to pond = 6.69 acres

Note The basin must be sized to treat all impervious surface runoff draining into the pond, not just the impervious surface from on-site development.

Drainage area = **14.19** acres @ **47.2%** impervious

Estimate the surface area required at pond normal pool elevation ==>

Wet Detention Basins are based on an minimum average depth of = **4.32** feet

		4.0	4.32	5.0
Lower Boundary =>	40.0	1.24		1.09
Site % impervious =>	47.2	1.43	1.37	1.25
Upper Boundary =>	50.0	1.51		1.31

Therefore, SA/DA required = **1.37**

Surface area required for main pool at normal pool = 8,495 ft²
= 0.20 acres
Surface area provided for total normal pool = 11,895 ft²
Surface area provided for main pool at normal pool = 8,977 ft²

DETERMINATION OF WATER QUALITY VOLUME

$$WQ_v = (P)(R_v)(A)/12$$

where,

WQ_v = water quality volume (in acre-ft)

R_v = 0.05+0.009(I) where I is percent impervious cover

A = area in acres

P = rainfall (in inches)

Input data:

Total area, A =	14.19	acres
Impervious area =	6.69	acres
Percent impervious cover, I =	47.2	%
Rainfall, P =	1.00	inches

Calculated values:

R _v =	0.47	
WQ _v =	0.56	acre-ft
=	24443	cf.

ASSOCIATED DEPTH IN POND

WQ_v = 24443 cf.

Stage / Storage Data:

Ks =	13490	
b =	1.189	
Zo =	310.00	
Volume in 1" rainfall =	24443	cf.

Calculated values:

Depth of WQv in Basin =	1.65	ft
=	19.79	inches
Elevation =	311.65	ft

DRAWDOWN ORIFICE DESIGN

D orifice = 2.25 inch
 # orifices = 1
 Ks = 13490
 b = 1.1886
 C_d orifice = 0.60
 Normal Pool Elevation = 310.00 feet
 Volume @ Normal Pool = 0 cf
 Orifice Invert = 310.00 feet
 WSEL @ 1" Runoff Volume = 311.65 feet

WSEL (feet)	Vol. Stored (cf)	Orifice Flow (cfs)	Avg. Flow (cfs)	Incr. Vol. (cf)	Incr. Time (sec)
311.65	24443	0.166			
311.51	21977	0.158	0.162	2466	15252
311.37	19554	0.150	0.154	2423	15753
311.23	17178	0.141	0.145	2376	16332
311.08	14853	0.132	0.137	2325	17012
310.94	12585	0.122	0.127	2268	17830
310.80	10380	0.112	0.117	2205	18842
310.66	8247	0.100	0.106	2133	20150
310.52	6199	0.087	0.093	2048	21949
310.38	4254	0.071	0.079	1945	24694
310.24	2444	0.050	0.061	1810	29867

Drawdown Time = 2.29 days

By comparison, if calculated by the average head over the orifice
 (assuming average head is one-third the total depth), the result would be:

Average driving head on orifice = 0.518 feet
 Orifice composite loss coefficient = 0.600
 Cross-sectional area of siphon = 0.028 sf

 Q = 0.0957 cfs

Drawdown Time = Volume / Flowrate / 86400 (sec/day)

Drawdown Time = 2.96 days

RISER ANTI-FLOTATION CALCULATION

Input Data ==>

Safety Factor:

Safety factor to use = 1.15 (recommend 1.15 or higher)

Concrete:

Concrete unit weight = 142.0 PCF

Note: NC Products lists unit wt. of manhole concrete at 142 PCF.

Riser:

Inside height of Riser = 5.50 feet
Inside length of riser = 5.00 feet
Inside width of riser = 5.00 feet
Wall thickness of riser = 6.00 inches
Base thickness of riser = 6.00 inches
Base length of riser = 6.00 feet
Base width of riser = 6.00 feet

Openings:

Total Orifice Area = 2.110 SF
OD of barrel exiting manhole = 44.00 inches
Size of drain pipe (if present) = 6.0 inches

Trash Rack:

Bottom Length = 8.40 feet
Bottom Width = 8.40 feet
Top Length = 2.10 feet
Top Width = 2.10 feet
Height = 2.00 feet
Trash Rack water displacement = 61.74 CF

Concrete Present in Riser Structure ==>

Total amount of concrete:

Base of Riser = 18.00 CF
Riser Walls = 60.50 CF

Adjust for openings:

Opening for Orifices = 1.06 CF
Opening for barrel = 5.28 CF
Opening for drain pipe = 0.10 CF

Total Concrete present, adjusted for openings = **72.067 CF**
Weight of concrete present = **10,234 lbs**

Amount of water displaced by Riser Structure ==>

Displacement by concrete =	72.07 CF
Displacement by open air in riser =	137.50 CF
Displacement by trash rack =	61.74 CF
Total water displaced by riser/barrel structure =	271.31 CF
Weight of water displaced =	16,930 lbs

Calculate size of base for riser assembly ==>

Length =	9.00 feet
Width =	9.00 feet
Thickness =	18 inches
Concrete Present =	121.50 CF

Check validity of base as designed ==>

Total Water Displaced =	374.81 CF
Total Concrete Present =	193.57 CF
Total Water Displaced =	23,388 lbs
Total Concrete Present =	27,487 lbs
Actual safety factor =	1.18 OK

Results of design ==>

Base length =	9.00 feet
Base width =	9.00 feet
Base Thickness =	18.00 inches
CY of concrete total in base =	4.50 CY
Concrete unit weight in added base >=	142.0 PCF

II. CALCULATION FOR RISER ANTI-FLOTATION STEEL

Input Data ==>

Anti-Floatation Block Length = 9.0 feet
Anti-Floatation Block Width = 9.0 feet
Anti-Floatation Block Thickness = 18 inches

A_{steel} to A_{concrete} Ratio = 0.0020 (recommend 0.0018 or hi

Cross-Section Calculations==>

Cross-Section Area* = 13.50 SF
Minimum Steel Area Required = 0.027 SF
3.89 SI

**Note: Assumes a "square" x-sec (L and W same)*

Rebar Calculations ==>

Bar Size	4	5	6	7	8
Diameter (inches)	0.500	0.625	0.750	0.875	1.000
X-Sec Area (SI)	0.196	0.307	0.442	0.601	0.785
Minimum Number of Bars	20	13	9	7	5


DESIGN OF RIPRAP OUTLET PROTECTION WORKSHEET

Project The Point
 Project No. AWH-20000
 Outlet ID SCM J

Date 11/23/2020
 Designer TKD

Flow, $Q_{10\text{-yr}}$ 23.0 cfs
 Slope, S 1.03 %
 Pipe Diameter, D_o 36 inches
 Pipe Diameter, D_o 3.0 feet
 Number of pipes 1
 Pipe separation 0 feet
 Manning's n 0.013

Figure 8.06.b.1



Zone from graph above = 3

Outlet pipe diameter 36 in. Length = 24.0 ft.
 Outlet flowrate 23.0 cfs Width = 9.0 ft.
 Outlet velocity 8.7 ft/sec Stone diameter = 13 in.
 Material = Class I Thickness = 22 in.

Zone	Material	Diameter	Thickness	Length	Width
1	Class A	3	9	4 x D(o)	3 x D(o)
2	Class B	6	22	6 x D(o)	3 x D(o)
3	Class I	13	22	8 x D(o)	3 x D(o)
4	Class I	13	22	8 x D(o)	3 x D(o)
5	Class II	23	27	10 x D(o)	3 x D(o)
6	Class II	23	27	10 x D(o)	3 x D(o)
7	Special study required				

1. Calculations based on NY DOT method - Pages 8.06.05 through 8.06.06 in NC Erosion Control Manual
2. Outlet velocity based on full-flow velocity